22019
100% CONSTRUCTION DOCUMENTS
01/31/2025

FIRST FLOOR FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR FINISH	FLOOR BASE	WALLS NORTH MAT.	WALLS NORTH FINISH	WALLS EAST MAT.	WALLS EAST FINISH	WALLS SOUTH MAT.	WALLS SOUTH FINISH	WALLS WEST MAT.	WALLS WEST FINISH	CEILING MATERIAL	CEILING FINISH	CEILING HEIGHT	REMARKS
C007	CORRIDOR	CONC	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	10'-0"	
100	GYM	WD	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	-	-	-	
101	EQ. STORAGE	CONC	-	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	10'-0"	
102	STAGE	WD	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	-	-	-	
103	TABLE/CHAIR STORAGE	CONC	-	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	10'-0"	
104	MEN	EPXF	-	CWT	-	CWT	-	CWT	-	CWT	-	GB	PTD	10'-0"	
105	WOMEN	EPXF	-	CWT	-	CWT	-	CWT	-	CWT	-	GB	PTD	10'-0"	
106	ENTRY VESTIBULE	LVT	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	9'-4"	
107	OPEN	CPT1	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	9'-4"	
108	CONCESSIONS	CPT1	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	9'-4"	
109	TELECOM	CPT1	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	ACT	-	9'-4"	
110	ELECTRICAL	CONC	-	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GB	PTD	9'-4"	
111	MECHANICAL	CONC	-	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GB	PTD	9'-4"	
112	FIRE RISER	LVT	RBR	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	GYP.BD.	PTD	-	-	9'-4"	
ROOMS BELOW WERE DELETED OR RENUMBERED ON SCOPE REDUCTION.															
113	OFFICE														
114	TELECOM														
115	SUPPLIES														
116	OFFICE														
117	PRINCIPAL														
118	ELECTRICAL														
119	WOMEN														
120	MECHANICAL														
121	MEN														
122	WARMING KITCHEN														
122A	CLOSET														
123	CLASSROOM														
123A	MECHANICAL														
124	CLASSROOM														
124A	MECHANICAL														
125	CLASSROOM														
125A	MECHANICAL														
126	CLASSROOM														
126A	MECHANICAL														
127	CLASSROOM														
127A	MECHANICAL														
128	CLASSROOM														
128A	MECHANICAL														
129	STORAGE														
130	BOYS														
130A	STOR. CLOSET														
131	GIRLS														
131A	JANITOR CLOSET														
132	BREAK OUT ROOM														
133	BREAK OUT ROOM														
C001	CORRIDOR														
C002	CORRIDOR														
C003	CORRIDOR														
C004	CORRIDOR														
C005	CORRIDOR														
C006	CORRIDOR														

ABBREVIATIONS

ACT	2'x2' SUSPENDED ACOUSTICAL CEILING SYSTEM
WD	WOOD FLOOR ASSEMBLY
CONC	CONCRETE – SEALED
CPT1	CARPET TILE 1
CPT2	CARPET TILE 2
CTB	CERAMIC TILE BASE
CWT	CERAMIC WALL TILE
EPXF	EPOXY TYPE FLOORING WITH INTEGRAL BASE
EQ	EQUIPMENT
EXP	EXPOSED STRUCTURE (PRIME AND PAINT)
GB	GYPSUM BOARD, CEILING/SOFFIT – TEXTURE: LEVEL 3, LIGHT TEXTURE, SEE SPECIFICATIONS
GBSC	SUSPENDED GYPSUM BOARD CEILING SYSTEM – TEXTURE: LEVEL 3, LIGHT TEXTURE, SEE SPECIFICATIONS
GYP.BD.	GYPSUM WALL BOARD – ABUSE RESISTANT – TEXTURED FINISH, SEE SPECIFICATIONS
MAT	MATERIAL
PC	CONCRETE – POLISHED
PTD	PAINT
RBR	4" RUBBER BASE
SCONC	CONCRETE – STAINED
SAF	SYNTHETIC ATHLETIC FLOORING
CTBB	CEMENTITIOUS TILE BACKER BOARD
VCT	VINYL COMPOSITION TILE
WGB	NEW WATER RESISTANT GYPSUM BOARD FOR THIN SET TILE

SEE SPECIFICATION FOR ADDITIONAL INFORMATION.

ROOM FINISH SCHEDULE GENERAL NOTES

1. FINISH COLOR SELECTIONS BY ARCHITECT
2. ALL NEW GYP. BOARD WALLS FINISH SEE SPECIFICATIONS.
3. PROVIDE AND INSTALL BLINDS AT ALL EXTERIOR WINDOWS.
4. ROOM SIGNAGE IS TO BE MOUNTED AT LATCH SIDE OF DOOR OUTSIDE OF ROOM.

ROOM FINISH SCHEDULE SPECIFIC NOTES (REMARKS COLUMN)

1. ALL VISIBLE PORTIONS OF CEILING AREA, INCLUDING STRUCTURE, DECKING AND BRACING, TO BE PRIMED AND PAINTED.
2. COMM./ELEC. ROOMS AND IT ROOM, INSTALL PAINTED FIRE RETARDED PLYWOOD FROM BASE TO CEILING, SEE SPECIFICATIONS.
3. ELEVATOR WALLS AND CEILING, SEE SPECIFICATIONS

A1 | ROOM FINISH SCHEDULE

SCALE: NTS

DAG ARCHITECTS

DAG Architects AR0009694
455 Harrison Ave Suite I Panama City, FL 32401
850.387.1671
www.DAGarchitects.com

100% CONSTRUCTION DOCUMENTS

A New Gymatorium for:
PALM BAY CHARTER SCHOOLS

1104 Balboa Avenue, Panama City, FL 32401

REVISIONS:

No.	Description	Date
1	SCOPE REDUCTION	2/6/2026

ALTERNATE
FINISH SCHEDULE

PROJECT NUMBER	22019
DATED	01/31/2025

A502.A

PLOT DATE: 2/6/2026 10:32:19 AM
DWG. LOCATION: G:\PC Harrison\Projects\2022 Projects\22019 Palm Bay Gymatorium\B-Design\B2Schematic\Design\B2Working\Docs\A502.A Finish Schedule.dwg
© 2021 DAG ARCHITECTS, INC. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE COPIED, REPRODUCED OR TRANSMITTED BY ANY MEANS WITHOUT WRITTEN PERMISSION OF DAG ARCHITECTS, INC. THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY AND COPYRIGHT OF DAG ARCHITECTS, INC. AND SHALL NOT BE USED ON ANY OTHER PROJECT OR LOCATION EXCEPT AS DESCRIBED ON THE DRAWINGS, WITHOUT THE PRIOR WRITTEN AGREEMENT OF DAG ARCHITECTS.