

PLUMBING LEGEND	
SYMBOL	DESCRIPTION
	SAN SANITARY LINE (ABOVE GROUND)
	V VENT PIPING
	CW COLD WATER
	HW HOT WATER
	HWR HOT WATER RETURN
	ISOLATION VALVE
	BALANCING VALVE
	FLOOR DRAIN
	PIPE DOWN
	PIPE UP
	POINT OF NEW CONNECTION
	FCO FLOOR CLEANOUT
	EXPANSION TANK
	RECIRCULATION PUMP

PLUMBING DRAWING LIST	
P0.1	PLUMBING SYMBOLS, LEGENDS AND ABBREVIATIONS
P0.2	PLUMBING SPECIFICATIONS
P0.3	PLUMBING DETAILS AND SCHEDULE
P1.0	PLUMBING SANITARY AND VENT PLAN AND RISER
P1.1	PLUMBING WATER PLAN AND RISER

CODE COMPLIANCE	
ALL WORK AND MATERIAL SHALL BE PERFORMED AND INSTALLED IN COMPLIANCE WITH THE FOLLOWING CODES AS ADOPTED AND AMENDED BY THE INSPECTING AUTHORITY. NOTHING IN THESE DRAWINGS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES OR OTHERS APPLICABLE TO THESE PROJECT:	
A.	2023 FLORIDA BUILDING CODE-BUILDING, 8TH EDITION
B.	2023 FLORIDA BUILDING CODE-PLUMBING, 8TH EDITION
C.	2023 FLORIDA BUILDING CODE-MECHANICAL, 8TH EDITION
D.	2023 FLORIDA BUILDING CODE-ENERGY CONSERVATION, 8TH EDITION
E.	NATIONAL ELECTRICAL CODE -2020
F.	2023 FLORIDA FIRE PREVENTION CODE - FIRE, 8TH EDITION

## PLUMBING ABBREVIATIONS

CW	COLD WATER
HW	HOT WATER
HWR	HOT WATER RETURN
SAN	SANITARY
WH-1	WATER HEATER
LAV	LAVATORY
WC	WATER CLOSET
TYP.	TYPICAL
DN	DOWN
FD	FLOOR DRAIN
MS	MOP SINK
RCP-1	RECIRCULATION PUMP
ET-1	EXPANSION TANK
DF	DRINKING FOUNTAIN
FCO	FLOOR CLEAN OUT
M	WATER SUB-METER
VIF	VERIFY IN FIELD

## PLUMBING SPECIFICATIONS

### 1. BASIC PLUMBING REQUIREMENTS, MATERIALS AND METHODS

#### 1.01 SCOPE

- PROVIDE ALL MATERIAL, TOOLS, SUPERVISION AND LABOR INCLUDING ALL MISCELLANEOUS AND INCIDENTAL ITEMS REQUIRED FOR COMPLETE AND OPERABLE PLUMBING INSTALLATIONS AS SHOWN OR DESCRIBED ON THE DRAWINGS AND IN THESE SPECIFICATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING AND NEW CONDITIONS AND MATERIALS WITHIN THE CONSTRUCTION AREA. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE OWNER'S SATISFACTION.
- OBTAIN ALL PERMITS, PAY ALL PERMIT FEES AND SCHEDULE ALL REQUIRED INSPECTIONS. COPIES OF ALL PERMITS AND INSPECTION CERTIFICATES SHALL BE FORWARDED TO THE OWNER FOR RECORD.
- THE GENERAL CONDITIONS OF THE CONTRACT AND ALL DIVISION 1 REQUIREMENTS APPLY TO THE WORK OF THIS SECTION.
- THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTING BID TO DETERMINE CONDITIONS AND THE EXTENT OF THE WORK. BY COMMENCING WORK, THE CONTRACTOR ACKNOWLEDGES HIS CONFIRMATION OF ALL CONDITIONS AS ACCEPTABLE WITH REFERENCE TO HIS CONTRACT, SCOPE OF WORK AND BID PRICE SUCH THAT NO ADDITIONAL COMPENSATION SHALL BE FORTHCOMING FOR UNFORESEEN EXISTING CONDITIONS.
- IN ALL AREAS SUBJECT TO FREEZING CONDITIONS, THE CONTRACTOR SHALL PROVIDE FREEZE PROTECTION FOR ALL DOMESTIC WATER PIPING INSTALLED UNDER HIS CONTRACT.
- ALL ELECTRICAL REQUIREMENTS SHALL BE COORDINATED WITH THE CONTRACTOR FOR ELECTRICAL WORK. THIS CONTRACTOR IS RESPONSIBLE FOR ALL LOW VOLTAGE WIRING FOR EQUIPMENT INSTALLED UNDER HIS CONTRACT. THE CONTRACTOR FOR ELECTRICAL WORK IS RESPONSIBLE FOR LINE VOLTAGE POWER WIRING ONLY.
- COLOR AND FINISH SELECTIONS FOR ALL MATERIALS, INCLUDING PAINTING OF PIPING, SHALL BE AS DIRECTED AND/OR APPROVED BY THE ARCHITECT.
- MINOR DETAILS NOT SHOWN OR SPECIFIED, BUT NECESSARY FOR THE PROPER AND ACCEPTABLE CONSTRUCTION, INSTALLATION OR OPERATION OF ANY PART OF THE WORK AS DETERMINED BY THE ENGINEER SHALL BE INCLUDED AS IF SPECIFIED OR INDICATED ON THE DRAWINGS.
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIREMENTS FOR THE INSTALLATION, CONNECTION, EXTENSION OR MODIFICATION TO ALL UTILITY SERVICES WITH RESPECTIVE PROVIDERS INCLUDING PAYMENT OF ALL ASSOCIATED FEES.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL PAINTING ASSOCIATED WITH CUTTING AND PATCHING. ALL PAINTING IN AREAS WITH COMPLETE FINISH RENOVATIONS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.

#### 1.02 SUBMITTALS

- SUBMITTAL REQUIREMENTS SHALL BE COORDINATED WITH THE ARCHITECT AND AUTHORITIES HAVING JURISDICTION, UNLESS OTHERWISE DIRECTED. CONTRACTOR SHALL PROVIDE SUBMITTALS AS LISTED BELOW.
  - PIPE AND FITTINGS
  - VALVES
  - HANGERS AND SUPPORTS
  - PLUMBING PIPING LAYOUT
  - TESTS
  - PLUMBING FIXTURES
  - WATER HEATERS & ACCESSORIES
  - FLOOR DRAINS
  - MIXING VALVES
  - ALL SCHEDULED PLUMBING EQUIPMENT
- SUBMITTALS FROM SUPPLIERS OR MANUFACTURERS WHICH DO NOT BEAR THE STAMP OF THE SUBMITTING CONTRACTOR INDICATING THAT THE CONTRACTOR HAS REVIEWED THE SUBMITTAL FOR CONFORMANCE WITH THE PROJECT REQUIREMENTS WILL BE RETURNED REJECTED.
- THE ENGINEER'S REVIEW OF SUBMITTALS IS A COURTESY WHICH DOES NOT RELIEVE THE CONTRACTOR FROM CONFORMING WITH THE CONSTRUCTION DOCUMENTS, REGARDLESS OF THE ACTION INDICATED BY THE SHOP DRAWINGS STAMP.
- SUBMIT PROOF OF APPROVAL AND/OR CONFIRMATION OF SATISFACTORY TEST RESULTS TO THE OWNER AND THE ARCHITECT.
- SUBMIT TO THE OWNER'S MAINTENANCE PERSONNEL OPERATION AND MAINTENANCE DATA FOR ALL SYSTEM COMPONENTS, SERVICING REQUIREMENTS, INSPECTION DATA, REPLACEMENT PART NUMBERS AND AVAILABILITY AND CONTACT INFORMATION FOR SERVICE/SUPPLY COMPANY.

#### 1.03 SUBSTITUTIONS

- ALL EQUIPMENT SHALL BE PRODUCTS OF THE SPECIFIED MANUFACTURER OR MANUFACTURERS. ALL BIDS SHALL BE BASED ON THE SPECIFIED MANUFACTURER OR MANUFACTURER'S EQUIPMENT. FOR SUBSTITUTIONS OF OTHER MANUFACTURER'S EQUIPMENT TO BE CONSIDERED, THE SUBSTITUTION MUST BE INDICATED PRIOR TO BIDDING WITH THE REASON FOR THE PROPOSED SUBSTITUTION IDENTIFIED, AND THE PROPOSED CREDIT TO THE OWNER INDICATED. THE ENGINEER SHALL DETERMINE THE ACCEPTABILITY OF ANY PROPOSED SUBSTITUTIONS.
- THE CONTRACTOR ASSUMES ALL RESPONSIBILITY FOR COORDINATING THE WORK OF OTHER TRADES WHICH MAY BE AFFECTED BY SUBSTITUTIONS, INCLUDING ALL RELATED COSTS.

#### 1.04 DEFINITIONS

- FURNISH: TO PURCHASE, PROCURE, ACQUIRE AND DELIVER, COMPLETE WITH RELATED ACCESSORIES.
- INSTALL: TO ERECT, MOUNT AND CONNECT, COMPLETE WITH RELATED ACCESSORIES.
- PROVIDE: TO FURNISH AND INSTALL.
- THIS CONTRACTOR: THE CONTRACTOR RESPONSIBLE FOR ALL PLUMBING WORK SHOWN AND SPECIFIED ON THESE DRAWINGS.
- REFER TO THE 2023 FLORIDA BUILDING CODE-PLUMBING, 8TH EDITION, FOR ADDITIONAL DEFINITIONS.

#### 1.05 DRAWINGS

- THE DRAWINGS ARE DIAGRAMMATIC AND ARE INTENDED TO ILLUSTRATE THE GENERAL ARRANGEMENT AND ROUTING OF PIPING AND GENERAL LOCATIONS OF EQUIPMENT. PRECISE LOCATIONS OF EQUIPMENT, RISERS AND STACKS, AND ROUTING AND ELEVATION OF ALL PIPING SYSTEMS SHALL BE COORDINATED IN THE FIELD WITH THE ARCHITECT, ARCHITECTURAL DRAWINGS, THE WORK OF OTHER TRADES, EXISTING AND NEW BUILDING CONDITIONS AND/OR THE PREFERENCES OF THE OWNER/TENANT AS CONSTRUCTION PROCEEDS. ALL PIPING SHALL BE INSTALLED CONCEALED IN FINISHED SPACES, UNLESS NOTED OTHERWISE.
- PROVIDE ALL NECESSARY INCIDENTAL MATERIALS AND ACCESSORIES REQUIRED TO MAKE THE WORK COMPLETE IN ALL RESPECTS, EVEN IF NOT PARTICULARLY SHOWN OR SPECIFIED.
- REFER TO PLUMBING EQUIPMENT/FIXTURE SCHEDULE ON THE DRAWINGS FOR ALL FIXTURE AND EQUIPMENT SPECIFICATIONS.
- REFER TO FIXTURE CONNECTION SIZE SCHEDULE FOR ALL FIXTURE ROUGHING SIZE REQUIREMENTS.
- VERIFY ALL INDICATED CONDITIONS BEFORE STARTING WORK AND REPORT ANY DISCREPANCIES. THE DRAWINGS REFLECT CONDITIONS WHICH CAN BE REASONABLY INTERPRETED FROM THE EXISTING VISIBLE CONDITIONS OR FROM DRAWINGS AND INFORMATION FURNISHED BY THE OWNER.
- LOCATE ALL FIXTURES AND EQUIPMENT AS PER THE FINAL ARCHITECTURAL DRAWINGS.

#### 1.06 PRODUCTS

- SANITARY AND VENT PIPING:
  - ABOVE / BELOW GRADE PIPING SHALL BE POLYVINYL CHLORIDE (PVC) PLASTIC PIPE IN IPS DIAMETERS, INCLUDING SCHEDULE 40, DR 22 (PS 200), AND DR 24 (PS 140) WITH A SOLID, CELLULAR CORE OR COMPOSITE WALL AS PER ASTM D2865, ASTM F891, ASTM F1488, CSA B181.2 STANDARDS.
  - SLOPE OF DRAINAGE SYSTEM SHALL BE 1/16" PER FOOT OF RUN FOR PIPE 8" OR LARGER (I.D.) AND 1/8" PER FOOT OF RUN FOR PIPE 3" TO 6" (I.D.) AND 1/4" PER FOOT OF RUN FOR PIPE 2-1/2" AND SMALLER (I.D.).
- DOMESTIC WATER PIPING:
  - WATER SUPPLY PIPING SHALL BE CROSS-LINKED POLYETHYLENE(PEX) PLASTIC TUBING AND COMPLY WITH ASTM F876, CSA B137.5.
  - ALL FITTINGS IN DOMESTIC WATER PIPING SHALL BE CROSS-LINKED POLYETHYLENE (PEX) PLASTIC TUBING AND COMPLY WITH ASSE 1061; ASTM F877; ASTM F1807; ASTM F1960; ASTM F2090; ASTM F2098; ASTM F2159; ASTM F2434; ASTM F2735, CSA B137.5.
  - THE ENTIRE DOMESTIC WATER DISTRIBUTION SYSTEM SHALL BE INSULATED INCLUDING ALL VALVES, FITTINGS, ETC.
  - COMPLY WITH NSF 61 FOR MATERIALS FOR WATER-SERVICE PIPING AND SPECIALTIES FOR DOMESTIC WATER.
  - ALL DOMESTIC WATER PIPING ABOVE GRADE SHALL BE INSULATED WITH FIRE-RETARDANT, FACTORY-APPLIED JACKET. PROVIDE COLD WATER PIPING WITH FACTORY-APPLIED VAPOR BARRIER. INSULATION REQUIREMENT SHOULD COMPLY WITH 2023 FBC-ENERGY CONSERVATION CODE SECTION C404.4 REFER BELOW C403.2.10 TABLE FOR MINIMUM PIPE INSULATION THICKNESS.

FLUID OPERATING TEMPERATURE RANGE AND USAGE (°F)	MINIMUM PIPE INSULATION THICKNESS						
	CONDUCTIVITY BTU·IN./ (H· FT2· °F)	MEAN RATING TEMPERATURE °F	NOMINAL PIPE OR TUBE SIZE (INCHES)				
			<1 1/2	1 to < 1 1/2	1 1/2 to < 4	4 to < 8	≥8
105-140	0.21-0.28	100	1.0	1.0	1.5	1.5	1.5
40-60	0.21-0.27	75	0.5	0.5	1.0	1.0	1.0

- AS PER 2023 FBC-ENERGY CONSERVATION CODE C404.6.1 HEATED-WATER CIRCULATION SYSTEMS SHALL BE PROVIDED WITH A CIRCULATION PUMP. THE SYSTEM RETURN PIPE SHALL BE A DEDICATED RETURN PIPE OR A COLD WATER SUPPLY PIPE. CONTROLS FOR CIRCULATING HOT WATER SYSTEM PUMPS SHALL START THE PUMP BASED ON THE IDENTIFICATION OF A DEMAND FOR HOT WATER WITHIN THE OCCUPANCY. THE CONTROLS SHALL AUTOMATICALLY TURN OFF THE PUMP WHEN THE WATER IN THE CIRCULATION LOOP IS AT THE DESIRED TEMPERATURE AND WHEN THERE IS NO DEMAND FOR HOT WATER.
- AS PER 2023 FBC-ENERGY CONSERVATION CODE, C404.7 WATER DISTRIBUTION SYSTEM HAVING ONE OR MORE RECIRCULATION PUMPS THAT PUMP WATER FROM A HEATED-WATER SUPPLY PIPE BACK TO THE HEATED-WATER SOURCE THROUGH A COLD-WATER SUPPLY PIPE SHALL BE A DEMAND RECIRCULATION WATER SYSTEM.PUMPS SHALL HAVE CONTROLS THAT COMPLY WITH BOTH OF THE FOLLOWING:
  - THE CONTROL SHALL START THE PUMP UPON RECEIVING A SIGNAL FROM THE ACTION OF A USER OF A FIXTURE,SENSING THE PRESENCE OF A USER OF A FIXTURE OR SENSING THE FLOW OF HOT OR TEMPERED WATER TO A FIXTURE.
  - THE CONTROL SHALL LIMIT THE TEMPERATURE OF THE WATER ENTERING THE COLD-WATER PIPING TO 104°F(40°C).
- HW SYSTEM PIPING IS DESIGNED AS PER MAXIMUM ALLOWED PIPE LENGTH METHOD AS PER 2023 FBC-ENERGY CONSERVATION CODE C404.5. THE HW PIPE LENGTH FROM THE NEAREST SOURCE OF HEATED WATER TO THE TERMINATION OF THE FIXTURE SUPPLY PIPE SHALL BE AS PER FOLLOWING TABLE C404.5.1.

NOMINAL PIPE SIZE (INCHES)	MAXIMUM PIPING LENGTH (FEET)	
	PUBLIC LAV	OTHER FIXTURES
1/2"	2'	43'
3/4"	0.5'	21'
1"	0.5'	13'
1 1/4"	0.5'	8'
1 1/2"	0.5'	6'
2" OR LARGER	0.5'	4'

#### C. ELECTRIC WATER HEATER

- TANKS SHALL BE 19 GALLONS CAPACITY AND SHALL HAVE 150 PSI WORKING PRESSURE AND BE EQUIPPED WITH EXTRUDED HIGH DENSITY ANODE.
- ALL INTERNAL SURFACES OF THE HEATER(S) EXPOSED TO WATER SHALL BE GLASS-LINED WITH AN ALKALINE BORO SILICATE COMPOSITION THAT HAS BEEN FUSED-TO-STEEL BY FIRING AT A TEMPERATURE RANGE OF 1400°F TO 1600°F.
- ELECTRIC HEATING ELEMENTS SHALL BE MEDIUM WATT DENSITY WITH ZINC PLATED COPPER SHEATH.
- EACH ELEMENT SHALL BE CONTROLLED BY AN INDIVIDUALLY MOUNTED THERMOSTAT AND HIGH TEMPERATURE CUT-OFF SWITCH. ALL INTERNAL CIRCUITS SHALL BE FUSED. THE OUTER JACKET SHALL BE OF BAKED ENAMEL FINISH AND SHALL BE PROVIDED WITH FULL SIZE CONTROL COMPARTMENT FOR PERFORMANCE OF SERVICE AND MAINTENANCE THROUGH HINGED FRONT PANEL AND SHALL ENCLOSE THE TANK WITH FOAM INSULATION. ELECTRICAL JUNCTION BOX WITH HEAVY DUTY TERMINAL BLOCK SHALL BE PROVIDED. THE DRAIN VALVE SHALL BE LOCATED IN THE FRONT FOR EASE OF SERVICING.

#### D. MIXING VALVES

- VALVE BODY SHALL BE MADE OF CAST BRASS. THE INTERNAL COMPONENTS SHALL BE MADE OF BRASS OR STAINLESS STEEL.
- TYPES A, C & D VALVES: VALVE SHUTS OFF IN FULL COLD POSITION AND MUST PASS THROUGH COLD RANGE BEFORE DELIVERING WARM, AND/OR HOT WATER. TEMPERATURE LIMIT SET AT 105°F MAXIMUM DELIVERY TEMPERATURE. IF ONE SUPPLY SHOULD FAIL, THE OTHER WILL AUTOMATICALLY AND INSTANTLY SHUT DOWN. DELIVERY CAPACITY IS 5GPM @ 45 PSIG DIFFERENTIAL.
- TYPES OF VALVES: TYPE A- THERMOSTATICALLY OPERATED BY MEANS OF BI-METALLIC STRIP, OR EXPANSION BELLOWS. TYPE B- SINGLE HANDLE MECHANICAL MIXER, OR INDIVIDUAL HOT AND COLD CONTROL VALVES; TYPE C- PRESSURE BALANCING SHOWER VALVE/PISTON OPERATED MIXING VALVE; TYPE D- BALANCED PRESSURE OPERATION, WITH INTEGRAL DIAL THERMOMETER INDICATING DELIVERED WATER TEMPERATURE.
- EACH ELEMENT SHALL BE CONTROLLED BY AN INDIVIDUALLY MOUNTED THERMOSTAT AND HIGH TEMPERATURE CUT-OFF SWITCH. ALL INTERNAL CIRCUITS SHALL BE FUSED. THE OUTER JACKET SHALL BE OF BAKED ENAMEL FINISH AND SHALL BE PROVIDED WITH FULL SIZE CONTROL COMPARTMENT FOR PERFORMANCE OF SERVICE AND MAINTENANCE THROUGH HINGED FRONT PANEL AND SHALL ENCLOSE THE TANK WITH FOAM INSULATION. ELECTRICAL JUNCTION BOX WITH HEAVY DUTY TERMINAL BLOCK SHALL BE PROVIDED. THE DRAIN VALVE SHALL BE LOCATED IN THE FRONT FOR EASE OF SERVICING.

#### E. HOT WATER RE-CIRCULATING PUMP

- IN-LINE PUMP: SINGLE STAGE VOLUTE TYPE PUMP SHALL BE MADE OF CAST IRON OR FORGED LEAD-FREE BRONZE IMPELLER.
- THE PUMP SHALL HAVE A GROUND AND POLISHED STEEL SHAFT WITH A HARDENED INTEGRAL THRUST COLLAR. THE SHAFT SHALL BE SUPPORTED BY TWO HORIZONTAL SLEEVE BEARINGS DESIGNED TO CIRCULATE OIL. THE PUMPS ARE TO BE EQUIPPED WITH A MECHANICAL SEAL WITH CARBON SEAL FACE ROTATING AGAINST CERAMIC SEAT. THE MOTOR SHALL BE NON-OVERLOADING AT ANY POINT ON PUMP CURVE.
- DIRECT CONNECT PUMP TO ELECTRIC MOTOR WITH FLEXIBLE COUPLING. THE MOTOR SHALL BE OF THE DRIP-PROOF, SLEEVE-BEARING, QUIET OPERATING, RUBBER-MOUNTED CONSTRUCTION. EQUIPMENT MOTOR WITH BUILT-IN THERMAL OVERLOAD PROTECTION.
- INSTALL IN-LINE CIRCULATING PUMPS BETWEEN PIPE FLANGES IN PIPING SYSTEMS. INSTALL OVERHEAD PIPE SUPPORTS, BOTH SIDES OF IN-LINE PUMPS, INSTALLED IN HORIZONTAL PIPING RUNS.
- HANGERS AND SUPPORTS:
  - HANGERS SHALL BE STANDARD STEEL, MALLEABLE OR WROUGHT IRON, AS MANUFACTURED BY GRINNELL OR APPROVED EQUAL, SUITABLE FOR THE TYPE OF CONSTRUCTION. PIPING SHALL NOT BE HUNG FROM OTHER PIPE.
  - SECTIONS OF INDIVIDUAL PIPE RUNS SHALL BE SUPPORTED BY CLEVIS HANGERS.
  - ALL EQUIPMENT SHALL BE PROVIDED WITH APPROVED SUPPORTS.
  - SUPPORTS SHALL BE PROVIDED IN STRICT ACCORDANCE WITH THE RECOMMENDATIONS OF THE PIPING MANUFACTURER.

#### G. VALVES

- PROVIDE GATE VALVES, BUTTERFLY OR BALL VALVES FOR SHUT-OFF DUTY ON MAIN AND BRANCH SUPPLY LINES. FOR ALL PIPE RUNS 2" AND SMALLER, PROVIDE BALL FOR ALL PIPE RUNS LARGER THAN 2" AND SMALLER THAN 4". PROVIDE GATE VALVES. PIPING 4" AND LARGER, PROVIDE BUTTERFLY VALVES FOR SHUT-OFF DUTY.
- ALL FIXTURES WITH THE EXCEPTION OF FLUSHOMETER-EQUIPPED WATER CLOSETS AND URINALS SHALL HAVE STOP VALVES TO CONTROL SUPPLY TO THE FIXTURE. WHERE SUPPLIES ARE EXPOSED PROVIDE CHROME-PLATED STOPS WITH CHROME-PLATED ESCUTCHEONS ON PIPING PENETRATIONS.
- ALL PLUMBING FIXTURES AND EQUIPMENT TO HAVE SHUT-OFF VALVES ON SUPPLY LINES.
- ALL BRANCH LINES TO HAVE SHUT-OFF VALVES.
- ALL VALVES SHALL BE ACCESSIBLE. PROVIDE ACCESS DOORS WHERE REQUIRED FOR VALVE ACCESS.
- PROVIDE GLOBE VALVES FOR THROTTLING/BALANCING OF THE HOT WATER CIRCULATING SYSTEM.

JEFFREY BAKER, ARCHITECT  
6373 SILVER STREAM LN  
FRISCO, TX 75036  
PH: 214.784.5014

NY ENGINEERS  
382 NE 191st ST, SUITE  
49674  
MIAMI, FL 33179



02.23.2026

TENANT FINISH FOR  
**JETSET PILATES**  
**TALLAHASSEE**  
440 N. MONROE STREET  
TALLAHASSEE, FL 32301

PROJECT NO JSP2509

START DATE 02.09.2026

DRAWN BY NYE

CHECKED BY NYE

NO.	DESCRIPTION	DATE
1	PERMIT	02.23.2026

PLUMBING SYMBOLS,  
LEGENDS AND  
ABBREVIATIONS

**P0.1**

copyright 2026

H. SLEEVES AND ESCUTCHEONS:

1. SLEEVES THROUGH STRUCTURAL CONCRETE MEMBERS AND SLEEVES FOR WALLS BELOW GRADE AND FLOORS ON GRADE SHALL BE STANDARD WEIGHT GALVANIZED SCHEDULE 40 STEEL PIPE. SLEEVES THROUGH OTHER THAN STRUCTURAL COMPONENTS OF THE BUILDING SHALL BE 20 GAGE GALVANIZED SHEET METAL WITH LOCK SEAM JOINTS. USG THERMAFIBER SAFING INSULATION SHALL BE INSTALLED BETWEEN PIPE AND SLEEVE.
2. PIPE ESCUTCHEON PLATES SHALL BE INSTALLED WHERE EXPOSED PIPING PASSES THROUGH WALLS, CEILINGS, AND FLOORS AND SHALL BE MINIMUM 20 GAGE STEEL. PROVIDE CHROME PLATED ESCUTCHEON PLATES IN FINISHED AREAS.

I. DRAINAGE ACCESSORIES

1. GENERAL:
  - a. INSTALL THE WORK OF THIS SECTION IN ACCORDANCE WITH THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS, UNLESS OTHERWISE SPECIFIED.
  - b. SECURE EXTERNAL COMPONENTS IN PLACE WITH VANDAL RESISTANT FASTENERS OR DEVICES WHICH CANNOT BE REMOVED WITHOUT SPECIAL TOOLS.

2. DEVICES:

- a. CLEANOUT & CLEANOUT PLUG
  - THREADED PIPE FITTING WITH GAS TIGHT CLEANOUT PLUG.
- LUBRICATE THREADS OF CLEANOUT PLUG WITH ANTI-SEIZE LUBRICANT BEFORE FINAL INSTALLATION.
- b. CLEANOUT WALL PLATE
  - IT SHOULD BE ROUND, STAINLESS STEEL OR POLISHED CHROME PLATED BRONZE COVER PLATE WITH STAINLESS STEEL VANDAL RESISTANT FASTENER TO SECURE TO CLEANOUT PLUG.

J. INSTALL PIPING TO CONSERVE BUILDING SPACE. DO NOT INTERFERE WITH USE OF BUILDING SPACE AND THE WORK OF OTHER TRADES. ALL PIPING RUN IN CEILING SHALL BE INSTALLED TIGHT TO THE STRUCTURE ABOVE.

K. VERIFY EXACT LOCATIONS OF ALL EXISTING UTILITIES.

L. INSTALL PIPING TO ALLOW FOR EXPANSION AND CONTRACTION WITHOUT STRESSING PIPE, JOINTS OR CONNECTED EQUIPMENT. PROVIDE PIPE ANCHORS, GUIDES AND EXPANSION JOINTS OR LOOPS IN ALL HOT WATER AND HOT WATER CIRCULATING MAIN SUPPLY PIPING AND SEGMENTS OF SUCH PIPE THAT EXCEED 30'-0" IN LENGTH.

M. IN ALL AREAS WITH FINISHED SURFACES, SYSTEM PIPING AND COMPONENTS SHALL BE CONCEALED ABOVE OR WITHIN FINISHED SURFACES.

N. INSTALL VALVES WITH STEMS UPRIGHT OR HORIZONTAL. REMOVE PROTECTIVE COATINGS PRIOR TO INSTALLATION.

O. REDUCTIONS IN PIPE SIZES SHALL BE MADE WITH ONE-PIECE REDUCING FITTINGS. BUSHINGS ARE NOT ACCEPTABLE. USE FLANGED FITTINGS AT THE BASE OF RISERS.

P. VENT PENETRATIONS THROUGH THE ROOF SHALL BE FLASHED.

Q. IF WATER PRESSURE EXCEEDS 80 PSI, A WATER PRESSURE REDUCING VALVE SHALL BE INSTALLED IN WATER PIPING AT CONNECTION TO MAIN.

R. PROVIDE DIELECTRIC FITTINGS BETWEEN DISSIMILAR METALS.

S. PIPE BACKFLOW PREVENTER DRAINS TO FLOOR DRAIN OR OTHER APPROVED INDIRECT WASTE SOURCE.

T. PROVIDE ACCESS DOORS/PANELS FOR SERVICE AND ACCESS TO ALL VALVES AND OTHER SYSTEM COMPONENTS ENCLOSED IN WALLS AND CEILINGS. ACCESS DOORS SHALL BE FURNISHED BY THIS CONTRACTOR, INSTALLED BY THE GENERAL CONTRACTOR.

U. ALL FIXTURES REQUIRING VACUUM BREAKERS SHALL BE EQUIPPED WITH INTEGRAL VACUUM BREAKERS.

V. ANY PENETRATIONS THROUGH FIRE RATED PARTITIONS, FLOORS, OR CEILINGS SHALL BE STEEL SLEEVED AND SEALED WITH 3M BRAND UL RATED FIRE BARRIER CAULK OR APPROVED EQUAL.

W. WHEN THE WATER PIPING SYSTEM IS COMPLETE, THOROUGHLY FLUSH ALL DIRT, SEDIMENT, SOLDER, ETC., OUT OF THE SYSTEM, REMOVING ALL STRAINERS, VALVE STEM SEATS, ETC., REQUIRED TO ACCOMPLISH THE FLUSHING.

X. AT ALL INDIRECT WASTE DRAINS, MAINTAIN AIR GAP AS REQUIRED BY CODE.

Y. CONNECT GAS PIPING TO ALL GAS-FIRED EQUIPMENT WITH GAS COCK, DIRT LEG AND UNION.

Z. FOR ALL GAS-FIRED EQUIPMENT, VERIFY INPUT RATING AND PRESSURE REQUIREMENTS. PROVIDE GAS PRESSURE REGULATORS VENTED TO THE BUILDING EXTERIOR ON GAS SUPPLY TO ALL EQUIPMENT REQUIRING LOWER THAN LINE GAS PRESSURE.

AA. ALL PIPING INSTALLED ON THE ROOF SHALL BE SUPPORTED BY "PILLOW BLOCK" PIPE STANDS AS MANUFACTURED BY MIRO INDUSTRIES, OR APPROVED EQUAL. WOOD PIPE SUPPORTS SHALL NOT BE ACCEPTABLE. PROVIDE TRAFFIC/WALK PADS BELOW ALL PIPE STANDS.

AB. INSTALL SLEEVES FOR ALL PIPES WHICH PASS THROUGH WALLS, FLOORS, AND CEILINGS. WHERE PIPES ARE TO BE INSULATED, THE SLEEVE SHALL BE LARGE ENOUGH TO ACCOMMODATE INSULATION. SLEEVES SHALL BE FLUSH WITH FINISHED SURFACES AT BOTH ENDS. ON FINISHED SURFACES IN EXPOSED AREAS PROVIDE ESCUTCHEONS COMPATIBLE WITH FINISH.

AC. PROVIDE WATER HAMMER ARRESTERS ON SUPPLY PIPING TO ALL FLUSHOMETER VALVES AND QUICK-CLOSING VALVES.

AD. UNLESS OTHERWISE INDICATED, TRAPS SEALS AT ALL FLOOR DRAINS SHALL BE MAINTAINED BY AN APPROVED TRAP PRIMING DEVICE.

AE. MAINTAIN ALL REQUIRED AND RECOMMENDED CLEARANCES FOR ALL PLUMBING SYSTEM COMPONENTS AND EQUIPMENT.

AF. MAINTAIN MINIMUM 10'-0" CLEARANCE BETWEEN ALL PLUMBING V.T.R.S AND ALL OUTDOOR AIR INTAKES. OFFSET VENT STACKS AND STACK VENTS IF AND AS REQUIRED BELOW ROOF TO MAINTAIN SUCH CLEARANCE WHETHER OR NOT SUCH OFFSET IS INDICATED ON THE DRAWINGS. PROVIDE ALL REQUIRED SEISMIC SUPPORTS.

2. INSTALLATION

2.01 GENERAL

A. ALL WORK WHICH REQUIRES DISRUPTION OF THE ROOFING SHALL BE DONE BY A CONTRACTOR CERTIFIED BY THE ROOFING MANUFACTURER AS REQUIRED TO MAINTAIN ANY EXISTING ROOF WARRANTIES.

B. EXTERIOR INSTALLATIONS TO BE WEATHER PROOF IN ALL RESPECTS.

C. EXTERIOR MATERIALS AND EQUIPMENT SHALL BE PAINTED TO PREVENT CORROSION, COLOR PER ARCHITECT.

D. COORDINATE THE PLUMBING WORK WITH ALL OTHER AFFECTED WORK AND THE CONSTRUCTION SCHEDULE.

E. REAM PIPE AND TUBE ENDS. REMOVE BURRS. BEVEL PLAIN AND FERROUS END PIPE.

F. REMOVE SCALE AND FOREIGN MATERIAL, FROM INSIDE AND OUTSIDE, BEFORE ASSEMBLY.

G. PREPARE PIPING CONNECTIONS TO EQUIPMENT WITH FLANGES AND UNIONS.

H. COORDINATION WITH THE WORK OF OTHER TRADES IS REQUIRED. PROVIDE OFFSETS IN PIPING SYSTEMS OR MINOR DEVIATIONS TO THE INDICATED PIPE ROUTING IN ORDER TO COORDINATE THE PLUMBING WORK WITH THE WORK OF ALL OTHER TRADES AND THE GENERAL BUILDING CONDITIONS.

I. NO DOMESTIC WATER PIPING SHALL BE INSTALLED IN UNHEATED SPACES.

J. PRIOR TO DISCONNECTING AND CONNECTING NEW WORK TO EXISTING SYSTEMS, THE PLUMBING CONTRACTOR SHALL NOTIFY THE PROPERTY MANAGER AND OFFER A PROPOSED SCHEDULE OF WORK. ESB WILL AUTHORIZE CONNECTIONS AND COORDINATE NECESSARY SHUT DOWNS AND DRAIN DOWNS AS REQUIRED. SHUT DOWNS AND DRAIN DOWNS MAY BE PERFORMED BY THE PLUMBING CONTRACTOR ONLY AFTER RECEIVING ESB AUTHORIZATION, AND SHOULD BE PERFORMED UNDER SUPERVISION OF ESB PERSONNEL. THREE (3) DAYS ADVANCE NOTICE TO THE PROPERTY MANAGER IS REQUIRED.

K. THE PLUMBING CONTRACTOR IS ADVISED THAT DUE TO THE NATURE OF THE OPERATIONS AND TENANT REQUIREMENTS, CONNECTIONS TO EXISTING SYSTEMS MAY HAVE TO BE MADE AFTER REGULAR WORKING HOURS. THE PROPERTY MANAGER WILL ADVISE THE PLUMBING CONTRACTOR OF THE TIME CONSTRAINTS UPON RECEIPT AND APPROVAL OF THE PLUMBING CONTRACTOR'S REQUEST FOR SHUT DOWN AND CONNECTION TO EXISTING SYSTEMS.

L. WHEN CONNECTING TO EXISTING STACKS AND RISERS, PROVISION IS TO BE MADE FOR FUTURE CONNECTIONS BY PROVIDING CAPPED AND VALVED OUTLETS ON DOMESTIC WATER RISERS AND PLUGGED OUTLETS ON THE SANITARY AND VENT STACKS.

2.02 ABOVE GRADE

A. INSTALL PLUMBING PIPING IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES TO ENSURE THAT PIPING COMPLIES WITH REQUIREMENTS AND SERVES INTENDED PURPOSES.

B. ROUTE PIPING IN AN ORDERLY MANNER, PLUMB AND PARALLEL TO BUILDING STRUCTURE, MAINTAIN GRADIENT, SLOPE PIPING AND ARRANGE SYSTEMS TO DRAIN. IN DOMESTIC WATER SYSTEMS, PROVIDE DRAIN VALVES AT MAIN SHUT-OFF VALVES AND ALL LOW POINTS IN PIPING.

C. USE EXISTING CONNECTIONS AT MAINS WHERE AVAILABLE FOR NEW BRANCH PIPING. LOCATE ALL RISERS AND PIPING BEFORE CONSTRUCTION COMMENCES AND TAKE CARE NOT TO DAMAGE SAME. ANY DAMAGE OCCURRING TO THE EXISTING PIPING WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

2.03 INSULATION

COVER ALL HOT WATER AND HOT WATER RECIRCULATION PIPE WITH 1" THICK FOR PIPE SIZE UP TO 1½" AND 1½" THICK FOR PIPE SIZE GREATER THAN 1½". INSTALL ALL INSULATION AS PER MANUFACTURERS RECOMMENDATIONS. ALL PIPE INSULATION SHALL COMPLY WITH 2023 FBC-ENERGY CONSERVATION CODE.

3. TESTING

A. AT THE COMPLETION OF THE PLUMBING WORK, COMPLETELY TEST THE ENTIRE INSTALLATION OF ALL SYSTEMS FOR PROPER OPERATION AND COMPLIANCE WITH APPLICABLE CODES AND LOCAL REQUIREMENTS. CORRECT ALL DEFICIENCIES FOUND.

B. TESTING OF THE INSTALLED SYSTEMS SHALL BE MADE BY THE CONTRACTOR IN THE PRESENCE OF A REPRESENTATIVE OF THE OWNER.

C. THE CONTRACTOR SHALL NOT COVER UP OR PERMANENTLY CONCEAL PIPING, DEVICES OR ANY PORTION OF NEWLY CONSTRUCTED PLUMBING SYSTEM(S) UNTIL SUCH SYSTEM, OR PORTION OF THE SYSTEM, HAS BEEN TESTED IN THE PRESENCE OF A REPRESENTATIVE OF THE OWNER AND INSPECTED BY THE LOCAL INSPECTOR AND APPROVED IN WRITING. EXCEPT PIPING PASSING THROUGH FLOORS, WALLS, PARTITIONS, OR BEAMS, FOR DISTANCES EQUAL TO THE THICKNESS OF SUCH FLOOR, WALL, PARTITION OR BEAM.

D. THIS CONTRACTOR SHALL NOTIFY THE VARIOUS DEPARTMENTS, BUREAUS AND INDIVIDUALS AT LEAST TWO WEEKS IN ADVANCE OF THE TIME THAT THE TESTS ARE TO BE CONDUCTED.

E. ALL DEFECTIVE PARTS SHALL BE REPLACED OR CORRECTED BY THIS CONTRACTOR AND AN EXTRA TEST OR TESTS SHALL BE MADE UNTIL THE OPERATION IS SATISFACTORY. ALL ARRANGEMENTS AND EXPENSES NECESSARY TO CONDUCT ALL TESTS REQUIRED BY THESE SPECIFICATIONS AND THE VARIOUS AGENCIES HAVING JURISDICTION OVER THE WORK INSTALLED UNDER THIS CONTRACT SHALL BE MADE BY THIS CONTRACTOR. NO EXTRA COMPENSATION WILL BE ALLOWED FOR THESE TESTS, THE COST THEREOF BEING INCLUDED IN THE LUMP SUM BID FOR THIS CONTRACT.

F. WHERE ANY EVIDENCE OF STOPPAGE IS FOUND IN PIPING OR EQUIPMENT, THIS CONTRACTOR SHALL DISCONNECT, CLEAN, REPAIR AND RECONNECT ALL OBSTRUCTED PIPING OR EQUIPMENT AND SHALL ALSO PAY FOR ALL NECESSARY CUTTING AND REPAIRS TO ADJOINING WORK.

G. ALL PIPING AND EQUIPMENT SHALL BE THOROUGHLY CLEANED INSIDE AND OUT, OF DIRT, CUTTINGS, OILS AND OTHER FOREIGN SUBSTANCES AND SHALL BE LEFT CLEAN.

H. ALL REQUIRED TESTS SHALL BE WITNESSED BY LOCAL AUTHORITIES AND THE OWNER'S REPRESENTATIVE.

I. ALL EQUIPMENT WILL BE FACTORY TESTED.

J. CONTRACTOR SHALL IDENTIFY TO THE OWNER'S REPRESENTATIVE ANY LEAKS OR DAMAGE THAT OCCURS AS A RESULT OF SYSTEM TESTING. CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO LIMIT ANY POTENTIAL DAMAGE. CORRECTIVE ACTION REQUIRED AS A RESULT OF TESTING SHALL BE PERFORMED IMMEDIATELY AND AT THE CONTRACTOR'S EXPENSE.

K. REPORT IN WRITING TO AUTHORITIES HAVING JURISDICTION, THE ARCHITECT AND THE OWNER THE RESULTS OF ALL TESTING.

L. TESTING REQUIREMENTS

- a. TEST ALL DOMESTIC WATER PIPING HYDROSTATICALLY TO 125 PSIG.
- b. HYDROSTATIC TEST PRESSURES SHALL REMAIN CONSTANT WITH NO VARIATION FOR 120 MINUTES.
- c. TESTS SHALL BE WITNESSED BY THE BUILDING ENGINEER.
- d. THE PLUMBING CONTRACTOR WILL BE HELD RESPONSIBLE FOR ALL DAMAGE DUE TO TEST FAILURES AND LEAKAGE IN THE TEST AREA AND ADJACENT TENANT OR ESB SPACES.

M. REFILL ENTIRE POTABLE HOT AND COLD WATER SUPPLY SYSTEM WITH CHLORINE SOLUTION (HTH OLIN CHEMICAL CORP.) AT A STRENGTH TO MEET STANDARDS OF THE DEPARTMENT OF HEALTH, AND FOR A PERIOD OF RETENTION AS STIPULATED.

N. THOROUGHLY FLUSH PIPING SYSTEM WITH FRESH WATER IMMEDIATELY PRIOR TO FINAL ACCEPTANCE.

4. WARRANTY

EQUIPMENT, MATERIALS AND WORKMANSHIP FURNISHED UNDER THIS CONTRACT SHALL BE GUARANTEED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE OF THE WORK BY THE OWNER. THE CONTRACTOR SHALL KEEP THE WORK IN GOOD REPAIR FOR ONE YEAR AFTER THE DATE OF FINAL APPROVAL. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, PROMPTLY CORRECT AND REPAIR ANY AND ALL BREAKS, FAILURES OR WEAR DUE TO FAULTY MATERIALS, WORKMANSHIP OR EQUIPMENT. ALL SETTLEMENTS OF SURFACES THAT MAY OCCUR WITHIN THAT PERIOD SHALL ALSO BE PROMPTLY REPAIRED.

JEFFREY BAKER, ARCHITECT  
6373 SILVER STREAM LN  
FRISCO, TX 75036  
PH: 214.784.5014

NY ENGINEERS  
382 NE 191st ST, SUITE  
49674  
MIAMI, FL 33179



02.23.2026

TENANT FINISH FOR  
**JETSET PILATES**  
**TALLAHASSEE**  
440 N. MONROE STREET  
TALLAHASSEE, FL 32301

PROJECT NO JSP2509

START DATE 02.09.2026


DRAWN BY NYE

CHECKED BY NYE

NO.	DESCRIPTION	DATE
1	PERMIT	02.23.2026

PLUMBING SPECIFICATIONS


**P0.2**  
copyright 2026




1 PIPE HANGER DETAILS  
NTS

PIPE SIZE	P.D.I. SYMBOL	FIXTURE UNIT RATINGS	A SIZE	B SIZE
1/2"	A	1 - 11	5"	1/2"
3/4"	B	12 - 32	5"	3/4"
1"	C	33 - 60	7"	1"
1-1/4"	D	61 - 113	7"	1-1/4"
1-1/2"	E	114 - 154	9"	1-1/2"
2"	F	155 - 330	9"	2"

NOTE: LOCATE ONE FOR EACH BANK OF FLUSHOMETER FIXTURES AT LAST FIXTURE PROVIDE A STAINLESS STEEL ACCESS DOOR FOR EACH SUFFICIENT IN SIZE TO ALLOW REPLACEMENT OF ARRESTOR AT A FUTURE DATE.



3 WATER HAMMER ARRESTOR DETAILS  
NTS




\*NOTE- COORDINATE WITH ARCHITECT FOR PATCHING/TRENCHING THE SLAB.


FLOOR CLEANOUT DETAIL NOTES

- LOCATE CLEANOUT AT THIS LOCATIONS:
  - BUILDING EXIT
  - AT TURNS OF PIPES GREATER THAN 45 DEGREES
  - AT 90° INTERVALS ON STRAIGHT RUNS
  - WHERE IS SHOWN ON PLANS
  - WHERE IS 18" CLEAR AROUND


5 FLOOR CLEANOUT DETAIL  
NTS



2 MXV - MIXING VALVE DETAIL  
NTS




4 PIPE SLEEVE THROUGH INTERIOR WALL DETAIL  
NTS



PIPE SIZE	ROD SIZE
1/2"	3/8"
3/4"	3/8"
1"	3/8"
1 1/4"	3/8"
1 1/2"	3/8"
2"	3/8"
2 1/2"	3/8"
3"	3/8"
4"	1/2"
5"	1/2"
6"	1/2"

6 HANGER DETAILS  
NTS

PLUMBING FIXTURE SCHEDULE							
MARK(S)	DESCRIPTION	MANUFACTURER / MODEL NO.	CW	HW	WASTE	VENT	REMARKS
<b>WATER HEATERS, EXPANSION TANKS, RECIRCULATION PUMPS</b>							
WH-1	WATER HEATER	AO SMITH DEL-20	-	-	-	-	CAPACITY : 19 GALLONS KW : 3 FLOW RATE : 17 GPH @72°F VPHHZ : 208/1/60
ET-1	EXPANSION TANK	AMTROL THERM-X-TROL ST-5C-DD	-	-	-	-	-
RCP-1	RECIRCULATION PUMP	TACO MODEL 006	3/4"	-	-	-	CARTRIDGE CIRCULATOR. BALANCE TO PROVIDE 2.5 GPM AGAINST 7 FEET OF H2O. TIME CLOCK TO CONTROL DURING OCCUPIED HOURS. PROVIDE TACO TEMPERATURE CONTROLLED AQUASTAT TO CONTROL PUMP.
<b>TOILET</b>							
WC	WATER CLOSET	KOHLER #K-44199 TOILET BOWL	3/4"	-	4"	2"	KOHLER K-4467 TOILET TANK WITH 1.28 GPF FLOW RATE.
<b>LAVATORIES</b>							
LAV	LAVATORY	MODO BATH SKU SIMPLE 6050A	1/2"	1/2"	2"	1-1/2"	SIMPLE 60.50A RECTANGULAR ADA COMPLIANT VESSEL OR WALL MOUNTED BATHROOM SINK, 23.6". FINISH : WHITE HIBISCUS SINGLE HAND CENTERSET FAUCET (MAKE: SIGNATURE HARDWARE, MODEL: #7574079), FINISH : POLISHED CHROME.
<b>FLOOR DRAIN</b>							
FD	FLOOR DRAIN	ZURN ZS415 W / TYPE BS STRAINER	-	-	3"	2"	PROVIDE BARRIER TYPE SEAL PROTECTION FOR ALL FLOOR DRAIN
<b>SERVICE SINKS</b>							
MS	MOP SINK	MUSTEE 63M	1/2"	1/2"	3"	2"	-
<b>DRINKING FOUNTAIN</b>							
DF	DRINKING FOUNTAIN	ELKAY LZSTL8WSVRLK	1/2"	-	2"	1-1/2"	-



7 WATER HEATER DETAILS  
NTS

JEFFREY BAKER, ARCHITECT  
6373 SILVER STREAM LN  
FRISCO, TX 75036  
PH: 214.784.5014

NY ENGINEERS  
382 NE 191st ST, SUITE  
49674  
MIAMI, FL 33179



02.23.2026

TENANT FINISH FOR  
**JETSET PILATES**  
**TALLAHASSEE**  
440 N. MONROE STREET  
TALLAHASSEE, FL 32301

PROJECT NO JSP2509

START DATE 02.09.2026

DRAWN BY NYE

CHECKED BY NYE

NO. DESCRIPTION DATE

1 PERMIT 02.23.2026

PLUMBING DETAILS  
AND SCHEDULE

**P0.3**  
copyright 2026

JEFFREY BAKER, ARCHITECT  
 6373 SILVER STREAM LN  
 FRISCO, TX 75036  
 PH: 214.784.5014

NY ENGINEERS  
 382 NE 191st ST, SUITE  
 49674  
 MIAMI, FL 33179



02.23.2026


TENANT FINISH FOR  
**JETSET PILATES**  
**TALLAHASSEE**  
 440 N. MONROE STREET  
 TALLAHASSEE, FL 32301

PROJECT NO	JSP2509	
START DATE	02.09.2026	
DRAWN BY	NYE	
CHECKED BY	NYE	
NO.	DESCRIPTION	DATE
1	PERMIT	02.23.2026

PLUMBING SANITARY AND  
 VENT PLAN AND RISER

**P1.0**


copyright 2026



**2 PLUMBING SANITARY AND VENT RISER**  
 SCALE : NTS


- GENERAL SANITARY AND VENT NOTES**
- PROVIDE ACCESS PANELS FOR CLEANOUTS AS REQUIRED.
  - CONTRACTOR TO FIELD VERIFY THE EXISTING SANITARY PIPING SIZE, LOCATION & INVERT ON SITE.
  - CONTRACTOR TO FIELD VERIFY THE EXISTING VENT PIPING SIZE & LOCATION ON SITE.
  - CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.

- SANITARY AND VENT PLAN KEY NOTES**
- CONNECT NEW 4" SANITARY LINE TO EXISTING 4" SANITARY STUB IN / NEARBY SPACE. CONTRACTOR TO FIELD VERIFY THE LOCATION AND INVERT OF EXISTING SANITARY STUB AND MAKE NECESSARY CHANGES IF REQUIRED.
  - CONNECT NEW 3" VENT LINE TO EXISTING VENT LINE IN / NEARBY SPACE OF ADEQUATE SIZE. CONTRACTOR TO FIELD VERIFY THE SIZE AND LOCATION OF EXISTING VENT LINE AND MAKE NECESSARY CHANGES IF REQUIRED.
  - CONTRACTOR TO PROVIDE BARRIER TYPE TRAP SEAL PROTECTION FOR ALL FLOOR DRAINS IF IT IS ALLOWED BY LOCAL AHJ IF NOT PROVIDE PORTABLE WATER SUPPLIED TRAP PRIMER FOR ALL FLOOR DRAIN.



**1 PLUMBING SANITARY AND VENT PLAN**  
 SCALE : 1/4"=1'-0"







2 PLUMBING WATER RISER  
P1.1 SCALE : NTS

- GENERAL WATER NOTES**
1. CW/HW/HWR PIPING TO BE PROVIDED WITH INSULATION AS PER 2023 FLORIDA BUILDING CODE-ENERGY CONSERVATION, 8TH EDITION (REFER SHEET P0.1).
  2. PROVIDE BRANCH PRV IF PRESSURE EXCEEDS 80 PSI.
  3. CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
  4. PROVIDE ACCESS PANELS FOR WATER HAMMER ARRESTOR, SHUT-OFF VALVES AS REQUIRED.
  5. REFER RISER DIAGRAM FOR WATER PIPE SIZING.
  6. CONTRACTOR SHALL VERIFY WITH THE AHJ THE EXACT MAKE, MODEL, AND TYPE OF ALL REQUIRED BACKFLOW PREVENTION DEVICES PRIOR TO INSTALLATION AND ACQUISITION, INCLUDING ANY SPECIFIC BFP REQUIREMENTS FOR EQUIPMENT.

- WATER PLAN KEY NOTES**
1. CONNECT NEW 1" COLD WATER PIPING TO EXISTING 1-1/2" COLD WATER STUB IN SPACE. PROVIDE NEW 1" WATER SUB-METER. CONTRACTOR TO FIELD VERIFY EXACT LOCATION OF THE EXISTING WATER STUB AND MAKE NECESSARY CHANGES IF REQUIRED.
  2. ROUTE WATER HEATER (WH-1) DRAIN TO MOP SINK.



1 PLUMBING WATER PLAN  
P1.1 SCALE : 1/4"=1'-0"



JEFFREY BAKER, ARCHITECT  
6373 SILVER STREAM LN  
FRISCO, TX 75036  
PH: 214.784.5014

NY ENGINEERS  
382 NE 191st ST, SUITE  
49674  
MIAMI, FL 33179



02.23.2026

TENANT FINISH FOR  
**JETSET PILATES  
TALLAHASSEE**  
440 N. MONROE STREET  
TALLAHASSEE, FL 32301

PROJECT NO	JSP2509	
START DATE	02.09.2026	
DRAWN BY	NYE	
CHECKED BY	NYE	
NO.	DESCRIPTION	DATE
1	PERMIT	02.23.2026

PLUMBING WATER PLAN  
AND RISER

**P1.1**  
copyright 2026