

A1 SITE PLAN
SCALE: 1" = 30'

GENERAL SITE NOTES

1. ALL SITE RELATED ACTIVITIES SHOULD BE COORDINATED WITH OWNER's DESIGNATED CONTACT PERSON FOR THIS BUILDING.
2. AT LEAST 3 WEEKS ADVANCE NOTICE SHOULD BE PROVIDED TO THE OWNER AND TO ANY AHJ AS REQUIRED BY CODE OR LOCAL ORDINANCE FOR ANY WORK IMPACTING TRAFFIC OR ACCESS TO THE SITE.
3. ALL BARRICADES, CRANES, RIGGING, SCAFFOLDING, PERMITS, SIGNAGE, AND TRAFFIC COORDINATION/REDIRECTION AS NEEDED TO SAFELY BRING IN ALL REQUIRED EQUIPMENT MUST BE PROVIDED BY THE CONTRACTOR.
4. THE CONTRACTOR WILL BE REQUIRED TO WORK WITHIN THE AREAS DESIGNATED BY THE OWNER.
5. ALL REQUIRED CRANE WORK (IF ANY) WILL BE REQUIRED TO OCCUR AFTER HOURS OR ON WEEKENDS UNLESS OTHERWISE APPROVED BY THE OWNER AND THE APPROPRIATE AHJ.
6. THE SITE PLAN PROVIDED IS SCHEMATIC IN NATURE. THERE ARE SLOPES ON THE SITE THAT COULD IMPACT SITE RELATED ACTIVITIES. THE CONTRACTOR IS RESPONSIBLE FOR VISITING THE SITE AND CONFIRMING ALL DIMENSIONS AND SLOPES THAT WILL IMPACT THEIR WORK.

SITE COORDINATION AND USE

1. THE CONTRACTOR WILL HAVE ACCESS TO THE BUILDING FROM 7AM TO 7PM, MONDAY THROUGH FRIDAY OTHER THAN NATIONAL HOLIDAYS. ALL WEEK-END AND AFTER-HOURS WORK MUST BE APPROVED BY AND COORDINATED IN ADVANCE w/ THE OWNER's DESIGNATED REPRESENTATIVE.
2. THE BUILDING WILL REMAIN PARTIALLY OCCUPIED DURING THE ENTIRE CONSTRUCTION PERIOD. MAINTAIN ALL EXISTING EGRESS ROUTES.
3. ALL WORK THAT REQUIRES A SHUT DOWN OF ANY BUILDING SYSTEM AND/OR SECURITY SYSTEM MUST BE SCHEDULED AT LEAST 7 DAYS IN ADVANCE w/ THE OWNER's DESIGNATED REPRESENTATIVE.
4. COORDINATE ALL ON-SITE STORAGE, STAGING AND AREA RESTRICTIONS IN ADVANCE w/ THE OWNER's DESIGNATED REPRESENTATIVE.
5. MEANS AND METHODS ARE UP TO THE CONTRACTOR. SHOULD ANY CRAIN WORK BE REQUIRED, THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL PERMITTING AND BARRICADES. SITING OF THE CRANE MUST BE COORDINATED IN ADVANCE w/ THE OWNER's DESIGNATED REPRESENTATIVE.
6. ALL CONTRACTORS, SUBCONTRACTORS AND THEIR EMPLOYEES MUST HAVE BACKGROUND CHECKS CONDUCTED IN ACCORDANCE WITH THE LATEST DMS REQUIREMENTS AS LISTED AT: https://dms-media.ccplatform.net/content/download/102442/file/Background%20Check%20Form%2004-2025.pdf

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE
KNOTT BUILDING
INTERIOR RENOVATIONS
PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

SITE PLAN

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS FULLY PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED BY DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A101



D1 GROUND FLOOR - DEMOLITION

SCALE: 3/32" = 1'-0"

N

GENERAL GROUND FLOOR PLAN NOTES:

ON THE GROUND FLOOR, AREA OF WORK SHALL ONLY BE LOCATED IN THE STAIRS. FLOORING SHALL REMAIN AS IS UNLESS OTHERWISE NOTED. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ANY WALL DAMAGED DURING THE RENOVATION WORK. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

DEMOLITION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- EXISTING WALL TO BE DEMOLISHED
- D# DEMO ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 GROUND FLOOR - RENOVATION

SCALE: 3/32" = 1'-0"

N

RENOVATION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- NEW NON-RATED WALL
- NEW NON-RATED SOUND WALL
- N## NEW ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

GROUND FLOOR - DEMOLITION & RENOVATION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, AND IS FOR A PROJECT PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT INTENDED BY DODSTONE ARCHITECTS, INC. WITHOUT THE EXPRESS CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A102



E1 FIRST FLOOR KEY PLAN
SCALE: 1/32" = 1'-0"



D1 SECOND FLOOR KEY PLAN
SCALE: 1/32" = 1'-0"

GENERAL DEMOLITION WORK NOTES:

1. IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED, CONTRACTOR SHALL REMOVE EXISTING FINISHES AND PREP SURFACES AS RECOMMENDED BY THE MANUFACTURER FOR NEW FINISH INSTALLATION.
2. REMOVE TV'S AND WALL MOUNTS IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED. PROTECT, STORE AND REINSTALL WHEN FINISH WORK IS COMPLETED.
3. REMOVE ALL EXISTING DOOR HARDWARE AS NOTED ON THE DOOR SCHEDULES AND PREPARE DOOR FOR NEW HARDWARE INSTALLATION.
4. SEE MEP SHEETS FOR REMOVAL AND REINSTALLATION OF EXISTING CEILING EQUIPMENT.
5. THE FINISH ON ALL EXTERIOR WALLS IN AREA OF WORK THAT CONTAIN WINDOWS TO BE REPLACED UNDER SEPARATE PROJECT/PERMIT SHALL BE REMOVED TO FACILITATE THE WINDOW & STRUCTURAL SUPPORT INSTALLATION.
6. ALL ITEMS ON EXISTING WALLS SHALL BE REMOVED AND THE WALL PATCHED, REPAIRED, AND PREPPED FOR NEW PAINT INSTALLATION. REINSTALL REMOVED ITEMS IN SAME LOCATION. COORDINATE WITH OWNER'S REPRESENTATIVE.

DEMOLITION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- EXISTING WALL TO BE DEMOLISHED
- D# DEMO ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.

DEMO PLAN KEYNOTES

D1	REMOVE EDGE OF EXISTING GYPSUM BOARD SOFFIT AND PREP AS REQUIRED TO EXTEND SOFFIT TO ACCOMMODATE NEW DUCTWORK.
D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING. INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D10	CONTRACTOR TO REMOVE EXISTING CABINETS, COUNTERS AND SHELVING AND ALL ASSOCIATED ATTACHMENT DEVICES.
D11	REMOVE WOOD TRIM AND SHELVING IN ALCOVE AND INFILL WALL NICHE.
D15	REMOVE EXISTING WALL BASE AND CARPET IN ROOM. PREP FLOOR IN ACCORDANCE TO MANUFACTUER'S RECOMMENDATION TO ACCEPT NEW FLOORING. SEE FINISH SCHEDULE.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.
D17	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. DOOR SHALL STAY IN SAME LOCATION, FLIP DOOR SWING AND INSTALL NEW HARDWARE.
D18	REMOVE EXISTING TACK BOARD AND INSTALL NEW DIGITAL SIGN AT NEW DOOR LOCATION.

GENERAL FIRST FLOOR PLAN NOTES:

ON THE FIRST FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED, EXTEND EXISTING SOFFITS, AND REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. REMOVE AND REPLACE EXISTING CABINETS IN THE AREA OF WORK. INSTALL NEW RADIAL DESK, LECTERN, WITNESS TABLES, REAR TABLES & CHAIR RAIL IN MEETING ROOM. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ALL ON WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. INSTALL NEW BULLET RESISTANT MATERIALS TO EAST WALL AS INDICATED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602. COORDINATE AV INSTALLATION w/ OWNER'S VENDOR.

GENERAL SECOND FLOOR PLAN NOTES:

ON THE SECOND FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.



A1 FIRST FLOOR - DEMOLITION
SCALE: 1/8" = 1'-0"

N



A3 SECOND FLOOR - DEMOLITION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIRST & SECOND FLOOR - DEMOLITION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, AND AS SUCH ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE INTENDED BY DODSTONE ARCHITECTS, INC. WITHOUT THE EXPRESSED CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A103

GENERAL DEMOLITION WORK NOTES:

1. IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED, CONTRACTOR SHALL REMOVE EXISTING FINISHES AND PREP SURFACES AS RECOMMENDED BY THE MANUFACTURER FOR NEW FINISH INSTALLATION.
2. REMOVE TV'S AND WALL MOUNTS IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED. PROTECT, STORE AND REINSTALL WHEN FINISH WORK IS COMPLETED.
3. REMOVE ALL EXISTING DOOR HARDWARE AS NOTED ON THE DOOR SCHEDULES AND PREPARE DOOR FOR NEW HARDWARE INSTALLATION.
4. SEE MEP SHEETS FOR REMOVAL AND REINSTALLATION OF EXISTING CEILING EQUIPMENT.
5. THE FINISH ON ALL EXTERIOR WALLS IN AREA OF WORK THAT CONTAIN WINDOWS TO BE REPLACED UNDER SEPARATE PROJECT/PERMIT SHALL BE REMOVED TO FACILITATE THE WINDOW & STRUCTURAL SUPPORT INSTALLATION.
6. ALL ITEMS ON EXISTING WALLS SHALL BE REMOVED AND THE WALL PATCHED, REPAIRED, AND PREPPED FOR NEW PAINT INSTALLATION. REINSTALL REMOVED ITEMS IN SAME LOCATION. COORDINATE WITH OWNER'S REPRESENTATIVE.

DEMO PLAN KEYNOTES

D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING, INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D7	REMOVE AND SALVAGE EXISTING DOOR FRAME. INFILL OPENING WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D8	REMOVE EXISTING TACK BOARD TO BE REPLACED WITH DIGITAL BOARDS AND PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DIGITAL BOARD AND ASSOCIATED BLOCKING. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.

GENERAL THIRD FLOOR PLAN NOTES:

ON THE THIRD FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

DEMOLITION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- EXISTING WALL TO BE DEMOLISHED
- D# DEMO ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 THIRD FLOOR - DEMOLITION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

SUBMISSION TITLE	#	DATE
SCHEMATIC DESIGN	01	08/12/25
100% CONSTRUCTION DOCUMENTS	02	10/09/25
100% PERMIT DOCUMENTS	03	10/31/25

REVISION TITLE	#	DATE

THIRD FLOOR - DEMOLITION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE FOR WHICH THEY WERE PREPARED WITHOUT THE EXPRESS WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A104

GENERAL DEMOLITION WORK NOTES:

1. IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED, CONTRACTOR SHALL REMOVE EXISTING FINISHES AND PREP SURFACES AS RECOMMENDED BY THE MANUFACTURER FOR NEW FINISH INSTALLATION.
2. REMOVE TV'S AND WALL MOUNTS IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED. PROTECT, STORE AND REINSTALL WHEN FINISH WORK IS COMPLETED.
3. REMOVE ALL EXISTING DOOR HARDWARE AS NOTED ON THE DOOR SCHEDULES AND PREPARE DOOR FOR NEW HARDWARE INSTALLATION.
4. SEE MEP SHEETS FOR REMOVAL AND REINSTALLATION OF EXISTING CEILING EQUIPMENT.
5. THE FINISH ON ALL EXTERIOR WALLS IN AREA OF WORK THAT CONTAIN WINDOWS TO BE REPLACED UNDER SEPARATE PROJECT/PERMIT SHALL BE REMOVED TO FACILITATE THE WINDOW & STRUCTURAL SUPPORT INSTALLATION.
6. ALL ITEMS ON EXISTING WALLS SHALL BE REMOVED AND THE WALL PATCHED, REPAIRED, AND PREPPED FOR NEW PAINT INSTALLATION. REINSTALL REMOVED ITEMS IN SAME LOCATION. COORDINATE WITH OWNER'S REPRESENTATIVE.

DEMO PLAN KEYNOTES

D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING, INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D8	REMOVE EXISTING TACK BOARD TO BE REPLACED WITH DIGITAL BOARDS AND PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DIGITAL BOARD AND ASSOCIATED BLOCKING. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D11	REMOVE WOOD TRIM AND SHELVING IN ALCOVE AND INFILL WALL NICHE.
D12	REMOVE AND SALVAGE EXISTING BLINDS FOR INSTALLATION IN NEW WINDOWS.
D13	REMOVE EXISTING CABINETRY AND APPLIANCES FOR INSTALLATION OF NEW WINDOWS. REMOVE EXISTING FINISHES IN THE ROOM AND PREP SURFACES FOR NEW FINISH INSTALLATION. SEE FINISH SCHEDULE.
D14	REMOVE EXISTING RAMP AND HANDRAIL AS NEEDED FOR INSTALLATION OF NEW WINDOWS AND STRUCTURAL SUPPORT. CONTRACTOR TO SALVAGE EXISTING HANDRAIL AND BASE TO REINSTALL AFTER WINDOW IS REPLACED IN SEPARATE WINDOW REPLACEMENT PROJECT. REMOVE EXISTING CARPET AND INSTALL NEW. ADJUST CEILINGS AS NECESSARY TO COMPLETE WINDOW AND SUPPORT FRAME INSTALLATION. REINSTALL RAMP AND FINISHES TO MATCH EXISTING.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.

GENERAL FOURTH FLOOR PLAN NOTES:

ON THE FOURTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

DEMOLITION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- EXISTING WALL TO BE DEMOLISHED
- D# DEMO ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 FOURTH FLOOR - DEMOLITION
SCALE: 1/8" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH FLOOR - DEMOLITION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT FOR WHICH THEY WERE PREPARED WITHOUT PERMISSION FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A105

GENERAL DEMOLITION WORK NOTES:

1. IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED, CONTRACTOR SHALL REMOVE EXISTING FINISHES AND PREP SURFACES AS RECOMMENDED BY THE MANUFACTURER FOR NEW FINISH INSTALLATION.
2. REMOVE TV'S AND WALL MOUNTS IN AREA OF WORK WHERE FINISHES ARE NOTED TO BE REPLACED. PROTECT, STORE AND REINSTALL WHEN FINISH WORK IS COMPLETED.
3. REMOVE ALL EXISTING DOOR HARDWARE AS NOTED ON THE DOOR SCHEDULES AND PREPARE DOOR FOR NEW HARDWARE INSTALLATION.
4. SEE MEP SHEETS FOR REMOVAL AND REINSTALLATION OF EXISTING CEILING EQUIPMENT.
5. THE FINISH ON ALL EXTERIOR WALLS IN AREA OF WORK THAT CONTAIN WINDOWS TO BE REPLACED UNDER SEPARATE PROJECT/PERMIT SHALL BE REMOVED TO FACILITATE THE WINDOW & STRUCTURAL SUPPORT INSTALLATION.
6. ALL ITEMS ON EXISTING WALLS SHALL BE REMOVED AND THE WALL PATCHED, REPAIRED, AND PREPPED FOR NEW PAINT INSTALLATION. REINSTALL REMOVED ITEMS IN SAME LOCATION. COORDINATE WITH OWNER'S REPRESENTATIVE.

DEMO PLAN KEYNOTES

D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING, INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D8	REMOVE EXISTING TACK BOARD TO BE REPLACED WITH DIGITAL BOARDS AND PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DIGITAL BOARD AND ASSOCIATED BLOCKING. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.

GENERAL FIFTH FLOOR PLAN NOTES:

ON THE FIFTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

DEMOLITION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- EXISTING WALL TO BE DEMOLISHED
- D# DEMO ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 FIFTH FLOOR - DEMOLITION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE
KNOTT BUILDING
INTERIOR RENOVATIONS
PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIFTH FLOOR - DEMOLITION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE FOR WHICH THEY WERE PREPARED WITHOUT PRIOR WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A106



E1 FIRST FLOOR KEY PLAN
SCALE: 1/32" = 1'-0"



D1 SECOND FLOOR KEY PLAN
SCALE: 1/32" = 1'-0"

FLOOR PLAN KEYNOTES	
R1	EXISTING METAL STUD WALL TO BE CONVERTED TO SOUND WALL SEPARATING ASSEMBLIES. CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF THE WALL AND EXTEND METAL STUDS TO THE BOTTOM OF THE DECK ABOVE. INSTALL SOUND BATT INSULATION AND EXTEND GYPSUM BOARD ON BOTH SIDES OF THE WALL PARTITION TO FLOOR DECK ABOVE. SOUND CAULK GYPSUM BOARD AT ALL POINTS WHERE IT MEETS THE FLOOR, ADJACENT WALL OR FLOOR DECK ABOVE. SEE A4/501 FOR DETAIL.
R2	INSTALL NEW SOUND WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WALL. EXTEND WALL TO FLOOR DECK ABOVE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS. SEE DETAIL D4/A501.
R3	INSTALL NEW WALL. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R4	ALIGN NEW WALL WITH EXISTING WALL OR COLUMN AS SHOWN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R5	ALIGN NEW WALL WITH EXISTING WINDOW OPENING. WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R6	INFILL EXISTING DOOR OPENING WITH WALL CONSTRUCTION TO MATCH EXISTING ADJACENT WALL. PRIME AND PAINT EXISTING WALL WITH A MINIMUM OF TWO (2) COATS EACH SIDE FROM CORNER-TO-CORNER.
R7	INSTALL NEW WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE.
R8	INSTALL RECESSED ELECTRONIC SIGN AND ANY REQUIRED BLOCKING ADJACENT TO ENTRANCE DOOR. LOW VOLTAGE CABLING TO BE INSTALLED TO EACH SIGN. MOUNT TOP OF SIGN FLUSH WITH TOP OF EXISTING ROOM NUMBER SIGN. SEE DETAIL ON A2/A501.
R9	INSTALL NEW CABINETS AND ALL ASSOCIATED ATTACHMENT DEVICES, POWER AND WATER TO ACCOMMODATE NEW LAYOUT.
R10	INSTALL NEW WALL BASE, CARPET AND CHAIR RAIL. CONTRACTOR TO STAIN NEW WALL BASE AND CHAIR RAIL TO MATCH THE EXISTING CHAIR RAIL AND WALL BASE IN MEETING RM 412.
R11	INSTALL THREE (3) LAYERS OF 7/16" BULLET RESISTANT FIBER GLASS PANELS AND ONE LAYER OF 5/8" TYPE "X" GYPSUM BOARD ALONG FACE OF EXISTING WALL. BULLET PROOF PANELS SHALL BE ARMORCORE BY WACO COMPOSITES OR ARCHITECT APPROVED EQUAL. SEE DETAIL A6/A501. FURR OUT WALL ABOVE BALLISTIC MATERIAL HEIGHT TO ALIGN FINISH SURFACES.
R12	FOLLOWING INSTALLATION OF NEW WINDOWS AND ASSOCIATED FRAME, FLASHING AND WATERPROOFING (UNDER SEPARATE CONTRACT BY OTHERS), INSTALL NEW INTERIOR STUD WALL. STUD WALL SHALL CONSIST OF METAL STUDS @ 16" O.C. (DEPTH TO MATCH EXISTING), INSULATION TO MATCH EXISTING, 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. INSTALL NEW SOLID SURFACE WINDOW SILLS. CONTRACTOR TO INSTALL NEW OR SALVAGED ROLLER SHADE WINDOW BLINDS.
R13	INSTALL 3/4" PLYWOOD BLOCKING IN WALL TO SUPPORT FURNITURE AND OVERHEAD CABINETS, COORDINATE EXACT LOCATION w/ OWNER'S FURNITURE VENDOR.
R14	INSTALL 3/4" PLYWOOD BLOCKING TO SUPPORT NEW MONITOR. COORDINATE EXACT LOCATION w/ OWNER'S AV CONTRACTOR AND AS INDICATED ON MEP SHEETS.
R16	INSTALL NEW LECTERN, WITNESS TABLES AND DAIS. COORDINATE CONCRETE FLOOR SLAB REMOVAL AND REINSTALLATION TO ACCOMMODATE NEW POWER AND DATA INSTALLATION. SEE DETAILS ON SHEET A413.
R17	CONTRACTOR TO COORDINATE w/ OWNER'S FURNITURE VENDOR FOR INSTALLATION OF CHAMBER SEATING.

GENERAL RENOVATION WORK NOTES:

1. INSTALL NEW FINISHES IN AREA OF WORK IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS TO INCLUDE FLOORING, BASE, AND ACT CEILING. PATCH AND REPAIR ANY VOIDS, NAIL HOLES OR DAMAGE IN EXISTING WALLS AND GYP. BD. CEILINGS. PRIME AND PAINT ALL NEW AND PREVIOUSLY PAINTED SURFACES A MINIMUM OF TWO (2) COATS THROUGHOUT THE AREA OF WORK CORNER-TO-CORNER.
2. REPLACE EXISTING DOOR HARDWARE ON DOORS AS NOTED IN THE DOOR SCHEDULES IN A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, & DOOR STOPS. CLEAN AND TOUCH-UP ALL STAINED DOORS. SEE DOOR SCHEDULE.
3. WHERE EXISTING WALL IS REMOVED TO ACCOMMODATE THE NEW WINDOW AND WINDOW SUPPORT, INSTALL NEW WALL, SOLID SURFACE WINDOW SILL, AND FINISHES. COORDINATE NEW WALL AND FINISH INSTALLATION WITH WINDOW REPLACEMENT PROJECT CONTRACTOR. REINSTALL ELECTRICAL DEVICES IN WALL AS SHOWN ON THE ELECTRICAL DRAWINGS.
4. REMOVE, STORE, AND REINSTALL ALL WALL MOUNTED MONITORS IN THE AREA OF WORK. MONITORS SHALL BE REINSTALLED IN SAME LOCATION. WHERE WALLS HAVE BEEN RECONFIGURED IN SUITES, SEE RENOVATION PLAN & ELECTRICAL PLANS FOR NEW LOCATIONS. INSTALL 3/4" PLYWOOD BLOCKING AS NEEDED IN NEW WALLS TO RECEIVE A MONITOR. COORDINATE WITH AV CONTRACTOR.
5. SEE MEP DRAWINGS FOR MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION SCOPE OF WORK.

RENOVATION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- NEW NON-RATED WALL
- NEW NON-RATED SOUND WALL
- N## NEW ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.

GENERAL FIRST FLOOR PLAN NOTES:

ON THE FIRST FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED, EXTEND EXISTING SOFFITS, AND REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. REMOVE AND REPLACE EXISTING CABINETS IN THE AREA OF WORK. INSTALL NEW RADIAL DESK, LECTURN, WITNESS TABLES, REAR TABLES & CHAIR RAIL IN MEETING ROOM. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. INSTALL NEW BULLET RESISTANT MATERIALS TO EAST WALL AS INDICATED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602. COORDINATE AV INSTALLATION w/ OWNER'S VENDOR.

GENERAL SECOND FLOOR PLAN NOTES:

ON THE SECOND FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.



A1 FIRST FLOOR - RENOVATION
SCALE: 1/8" = 1'-0"



A3 SECOND FLOOR - RENOVATION
SCALE: 1/8" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIRST & SECOND FLOOR - RENOVATION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT AUTHORIZED BY DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A107

GENERAL RENOVATION WORK NOTES:

1. INSTALL NEW FINISHES IN AREA OF WORK IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS TO INCLUDE FLOORING, BASE, AND ACT CEILING. PATCH AND REPAIR ANY VOIDS, NAIL HOLES OR DAMAGE IN EXISTING WALLS AND GYP. BD. CEILINGS. PRIME AND PAINT ALL NEW AND PREVIOUSLY PAINTED SURFACES A MINIMUM OF TWO (2) COATS THROUGHOUT THE AREA OF WORK CORNER-TO-CORNER.
2. REPLACE EXISTING DOOR HARDWARE ON DOORS AS NOTED IN THE DOOR SCHEDULES IN A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, & DOOR STOPS. CLEAN AND TOUCH-UP ALL STAINED DOORS. SEE DOOR SCHEDULE.
3. WHERE EXISTING WALL IS REMOVED TO ACCOMMODATE THE NEW WINDOW AND WINDOW SUPPORT, INSTALL NEW WALL, SOLID SURFACE WINDOW SILL, AND FINISHES. COORDINATE NEW WALL AND FINISH INSTALLATION WITH WINDOW REPLACEMENT PROJECT CONTRACTOR. REINSTALL ELECTRICAL DEVICES IN WALL AS SHOWN ON THE ELECTRICAL DRAWINGS.
4. REMOVE, STORE, AND REINSTALL ALL WALL MOUNTED MONITORS IN THE AREA OF WORK. MONITORS SHALL BE REINSTALLED IN SAME LOCATION. WHERE WALLS HAVE BEEN RECONFIGURED IN SUITES, SEE RENOVATION PLAN & ELECTRICAL PLANS FOR NEW LOCATIONS. INSTALL 3/4" PLYWOOD BLOCKING AS NEEDED IN NEW WALLS TO RECEIVE A MONITOR. COORDINATE WITH AV CONTRACTOR.
5. SEE MEP DRAWINGS FOR MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION SCOPE OF WORK.

FLOOR PLAN KEYNOTES

R1	EXISTING METAL STUD WALL TO BE CONVERTED TO SOUND WALL SEPARATING ASSEMBLIES. CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF THE WALL AND EXTEND METAL STUDS TO THE BOTTOM OF THE DECK ABOVE. INSTALL SOUND BATT INSULATION AND EXTEND GYPSUM BOARD ON BOTH SIDES OF THE WALL PARTITION TO FLOOR DECK ABOVE. SOUND CAULK GYPSUM BOARD AT ALL POINTS WHERE IT MEETS THE FLOOR, ADJACENT WALL OR FLOOR DECK ABOVE. SEE A4/501 FOR DETAIL.
R2	INSTALL NEW SOUND WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WALL. EXTEND WALL TO FLOOR DECK ABOVE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS. SEE DETAIL D4/ A501.
R4	ALIGN NEW WALL WITH EXISTING WALL OR COLUMN AS SHOWN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R5	ALIGN NEW WALL WITH EXISTING WINDOW OPENING. WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R6	INFILL EXISTING DOOR OPENING WITH WALL CONSTRUCTION TO MATCH EXISTING ADJACENT WALL. PRIME AND PAINT EXISTING WALL WITH A MINIMUM OF TWO (2) COATS EACH SIDE FROM CORNER-TO-CORNER.
R7	INSTALL NEW WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE.
R8	INSTALL RECESSED ELECTRONIC SIGN AND ANY REQUIRED BLOCKING ADJACENT TO ENTRANCE DOOR. LOW VOLTAGE CABLING TO BE INSTALLED TO EACH SIGN. MOUNT TOP OF SIGN FLUSH WITH TOP OF EXISTING ROOM NUMBER SIGN. SEE DETAIL ON A2/A501.
R12	FOLLOWING INSTALLATION OF NEW WINDOWS AND ASSOCIATED FRAME, FLASHING AND WATERPROOFING (UNDER SEPARATE CONTRACT BY OTHERS), INSTALL NEW INTERIOR STUD WALL. STUD WALL SHALL CONSIST OF METAL STUDS @ 16" O.C. (DEPTH TO MATCH EXISTING), INSULATION TO MATCH EXISTING, 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. INSTALL NEW SOLID SURFACE WINDOW SILLS. CONTRACTOR TO INSTALL NEW OR SALVAGED ROLLER SHADE WINDOW BLINDS.
R13	INSTALL 3/4" PLYWOOD BLOCKING IN WALL TO SUPPORT FURNITURE AND OVERHEAD CABINETS, COORDINATE EXACT LOCATION w/ OWNER'S FURNITURE VENDOR.
R14	INSTALL 3/4" PLYWOOD BLOCKING TO SUPPORT NEW MONITOR. COORDINATE EXACT LOCATION w/ OWNER'S AV CONTRACTOR AND AS INDICATED ON MEP SHEETS.
R18	ALIGN NEW WALL AND POCKET DOOR w/ EXISTING WALL AND COLUMN. NEW WALL SHALL CONSIST OF 6" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WALL. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.

GENERAL THIRD FLOOR PLAN NOTES:

ON THE THIRD FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

RENOVATION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- NEW NON-RATED WALL
- NEW NON-RATED SOUND WALL
- N### NEW ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 THIRD FLOOR - RENOVATION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE
KNOTT BUILDING
INTERIOR RENOVATIONS
PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

THIRD FLOOR - RENOVATION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT INTENDED HEREIN WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A108

GENERAL RENOVATION WORK NOTES:

1. INSTALL NEW FINISHES IN AREA OF WORK IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS TO INCLUDE FLOORING, BASE, AND ACT CEILING. PATCH AND REPAIR ANY VOIDS. NAIL HOLES OR DAMAGE IN EXISTING WALLS AND GYP. BD. CEILINGS. PRIME AND PAINT ALL NEW AND PREVIOUSLY PAINTED SURFACES A MINIMUM OF TWO (2) COATS THROUGHOUT THE AREA OF WORK CORNER-TO-CORNER.
2. REPLACE EXISTING DOOR HARDWARE ON DOORS AS NOTED IN THE DOOR SCHEDULES IN A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, & DOOR STOPS. CLEAN AND TOUCH-UP ALL STAINED DOORS. SEE DOOR SCHEDULE.
3. WHERE EXISTING WALL IS REMOVED TO ACCOMMODATE THE NEW WINDOW AND WINDOW SUPPORT, INSTALL NEW WALL, SOLID SURFACE WINDOW SILL, AND FINISHES. COORDINATE NEW WALL AND FINISH INSTALLATION WITH WINDOW REPLACEMENT PROJECT CONTRACTOR. REINSTALL ELECTRICAL DEVICES IN WALL AS SHOWN ON THE ELECTRICAL DRAWINGS.
4. REMOVE, STORE, AND REINSTALL ALL WALL MOUNTED MONITORS IN THE AREA OF WORK. MONITORS SHALL BE REINSTALLED IN SAME LOCATION. WHERE WALLS HAVE BEEN RECONFIGURED IN SUITES, SEE RENOVATION PLAN & ELECTRICAL PLANS FOR NEW LOCATIONS. INSTALL 3/4" PLYWOOD BLOCKING AS NEEDED IN NEW WALLS TO RECEIVE A MONITOR. COORDINATE WITH AV CONTRACTOR.
5. SEE MEP DRAWINGS FOR MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION SCOPE OF WORK.

FLOOR PLAN KEYNOTES

R1	EXISTING METAL STUD WALL TO BE CONVERTED TO SOUND WALL SEPARATING ASSEMBLIES. CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF THE WALL AND EXTEND METAL STUDS TO THE BOTTOM OF THE DECK ABOVE. INSTALL SOUND BATT INSULATION AND EXTEND GYPSUM BOARD ON BOTH SIDES OF THE WALL PARTITION TO FLOOR DECK ABOVE. SOUND CAULK GYPSUM BOARD AT ALL POINTS WHERE IT MEETS THE FLOOR, ADJACENT WALL OR FLOOR DECK ABOVE. SEE A4/501 FOR DETAIL.
R2	INSTALL NEW SOUND WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WALL. EXTEND WALL TO FLOOR DECK ABOVE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS. SEE DETAIL D4/A501.
R4	ALIGN NEW WALL WITH EXISTING WALL OR COLUMN AS SHOWN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R6	INFILL EXISTING DOOR OPENING WITH WALL CONSTRUCTION TO MATCH EXISTING ADJACENT WALL. PRIME AND PAINT EXISTING WALL WITH A MINIMUM OF TWO (2) COATS EACH SIDE FROM CORNER-TO-CORNER.
R7	INSTALL NEW WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE.
R8	INSTALL RECESSED ELECTRONIC SIGN AND ANY REQUIRED BLOCKING ADJACENT TO ENTRANCE DOOR. LOW VOLTAGE CABLING TO BE INSTALLED TO EACH SIGN. MOUNT TOP OF SIGN FLUSH WITH TOP OF EXISTING ROOM NUMBER SIGN. SEE DETAIL ON A2/A501.
R12	FOLLOWING INSTALLATION OF NEW WINDOWS AND ASSOCIATED FRAME, FLASHING AND WATERPROOFING (UNDER SEPARATE CONTRACT BY OTHERS), INSTALL NEW INTERIOR STUD WALL. STUD WALL SHALL CONSIST OF METAL STUDS @ 16" O.C. (DEPTH TO MATCH EXISTING), INSULATION TO MATCH EXISTING, 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. INSTALL NEW SOLID SURFACE WINDOW SILLS. CONTRACTOR TO INSTALL NEW OR SALVAGED ROLLER SHADE WINDOW BLINDS.
R13	INSTALL 3/4" PLYWOOD BLOCKING IN WALL TO SUPPORT FURNITURE AND OVERHEAD CABINETS, COORDINATE EXACT LOCATION w/ OWNER'S FURNITURE VENDOR.
R14	INSTALL 3/4" PLYWOOD BLOCKING TO SUPPORT NEW MONITOR. COORDINATE EXACT LOCATION w/ OWNER'S AV CONTRACTOR AND AS INDICATED ON MEP SHEETS.
R15	INSTALL NEW RAMP, FINISHES AND SALVAGED RAILING TO MATCH EXISTING RAMP THAT WAS REMOVED TO ACCOMMODATE NEW WINDOW INSTALLATION. PRIME AND PAINT ALL WALLS AFFECTED BY CONSTRUCTION WITH A MINIMUM OF TWO (2) COATS FROM CORNER TO CORNER.
R19	REINSTALL SALVAGED CABINETRY AND APPLIANCES FOR INSTALLATION IN ROOM. INSTALL NEW FINISHES THROUGHOUT ROOM. SEE FINISH SCHEDULE.
R20	INSTALL NEW WALL. NEW WALL SHALL CONSIST OF 6" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TILE BACKER BOARD ON SIDE OF WALL IN PREPARATION FOR NEW TILE INSTALLATION.
R21	INSTALL NEW SOLID SURFACE SILLS. PATCH, PRIME AND PAINT A MINIMUM OF (2) COATS FROM CORNER-TO-CORNER

GENERAL FOURTH FLOOR PLAN NOTES:

ON THE FOURTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

RENOVATION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- NEW NON-RATED WALL
- NEW NON-RATED SOUND WALL
- N## NEW ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 FOURTH FLOOR - RENOVATION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH FLOOR - RENOVATION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED BY DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A109

GENERAL RENOVATION WORK NOTES:

1. INSTALL NEW FINISHES IN AREA OF WORK IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS TO INCLUDE FLOORING, BASE, AND ACT CEILING. PATCH AND REPAIR ANY VOIDS, NAIL HOLES OR DAMAGE IN EXISTING WALLS AND GYP. BD. CEILINGS. PRIME AND PAINT ALL NEW AND PREVIOUSLY PAINTED SURFACES A MINIMUM OF TWO (2) COATS THROUGHOUT THE AREA OF WORK CORNER-TO-CORNER.
2. REPLACE EXISTING DOOR HARDWARE ON DOORS AS NOTED IN THE DOOR SCHEDULES IN A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, & DOOR STOPS. CLEAN AND TOUCH-UP ALL STAINED DOORS. SEE DOOR SCHEDULE.
3. WHERE EXISTING WALL IS REMOVED TO ACCOMMODATE THE NEW WINDOW AND WINDOW SUPPORT, INSTALL NEW WALL, SOLID SURFACE WINDOW SILL, AND FINISHES. COORDINATE NEW WALL AND FINISH INSTALLATION WITH WINDOW REPLACEMENT PROJECT CONTRACTOR. REINSTALL ELECTRICAL DEVICES IN WALL AS SHOWN ON THE ELECTRICAL DRAWINGS.
4. REMOVE, STORE, AND REINSTALL ALL WALL MOUNTED MONITORS IN THE AREA OF WORK. MONITORS SHALL BE REINSTALLED IN SAME LOCATION. WHERE WALLS HAVE BEEN RECONFIGURED IN SUITES, SEE RENOVATION PLAN & ELECTRICAL PLANS FOR NEW LOCATIONS. INSTALL 3/4" PLYWOOD BLOCKING AS NEEDED IN NEW WALLS TO RECEIVE A MONITOR. COORDINATE WITH AV CONTRACTOR.
5. SEE MEP DRAWINGS FOR MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION SCOPE OF WORK.

FLOOR PLAN KEYNOTES

R1	EXISTING METAL STUD WALL TO BE CONVERTED TO SOUND WALL SEPARATING ASSEMBLIES. CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF THE WALL AND EXTEND METAL STUDS TO THE BOTTOM OF THE DECK ABOVE. INSTALL SOUND BATT INSULATION AND EXTEND GYPSUM BOARD ON BOTH SIDES OF THE WALL PARTITION TO FLOOR DECK ABOVE. SOUND CAULK GYPSUM BOARD AT ALL POINTS WHERE IT MEETS THE FLOOR, ADJACENT WALL OR FLOOR DECK ABOVE. SEE A4/501 FOR DETAIL.
R2	INSTALL NEW SOUND WALL AS SHOWN IN NEW FLOOR PLAN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WALL. EXTEND WALL TO FLOOR DECK ABOVE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS. SEE DETAIL D4/ A501.
R3	INSTALL NEW WALL. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R4	ALIGN NEW WALL WITH EXISTING WALL OR COLUMN AS SHOWN. NEW WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R5	ALIGN NEW WALL WITH EXISTING WINDOW OPENING. WALL SHALL CONSIST OF 3 5/8" LT GAUGE METAL STUDS AT 16" O.C. WITH ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE. PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
R6	INFILL EXISTING DOOR OPENING WITH WALL CONSTRUCTION TO MATCH EXISTING ADJACENT WALL. PRIME AND PAINT EXISTING WALL WITH A MINIMUM OF TWO (2) COATS EACH SIDE FROM CORNER-TO-CORNER.
R8	INSTALL RECESSED ELECTRONIC SIGN AND ANY REQUIRED BLOCKING ADJACENT TO ENTRANCE DOOR. LOW VOLTAGE CABLING TO BE INSTALLED TO EACH SIGN. MOUNT TOP OF SIGN FLUSH WITH TOP OF EXISTING ROOM NUMBER SIGN. SEE DETAIL ON A2/A501.
R12	FOLLOWING INSTALLATION OF NEW WINDOWS AND ASSOCIATED FRAME, FLASHING AND WATERPROOFING (UNDER SEPARATE CONTRACT BY OTHERS), INSTALL NEW INTERIOR STUD WALL. STUD WALL SHALL CONSIST OF METAL STUDS @ 16" O.C. (DEPTH TO MATCH EXISTING), INSULATION TO MATCH EXISTING, 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. INSTALL NEW SOLID SURFACE WINDOW SILLS. CONTRACTOR TO INSTALL NEW OR SALVAGED ROLLER SHADE WINDOW BLINDS.
R13	INSTALL 3/4" PLYWOOD BLOCKING IN WALL TO SUPPORT FURNITURE AND OVERHEAD CABINETS, COORDINATE EXACT LOCATION w/ OWNER'S FURNITURE VENDOR.
R14	INSTALL 3/4" PLYWOOD BLOCKING TO SUPPORT NEW MONITOR. COORDINATE EXACT LOCATION w/ OWNER'S AV CONTRACTOR AND AS INDICATED ON MEP SHEETS.

GENERAL FIFTH FLOOR PLAN NOTES:

ON THE FIFTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

RENOVATION LEGEND

- EXISTING 2-HR RATED STUD WALL
- EXISTING 2-HR RATED MASONRY OR CONCRETE WALL
- EXISTING NON-RATED WALL
- NEW NON-RATED WALL
- NEW NON-RATED SOUND WALL
- N## NEW ELEMENTS NOTE MARKER

NOTE: MAINTAIN ALL EXISTING RATED ASSEMBLIES. EXISTING RATED WALLS SPECIFIC TO THE THIS PROJECT HAVE BEEN IDENTIFIED AND ARE INDICATED AS NOTED. NOT ALL RATED WALLS ARE IDENTIFIED. WHERE WALLS HAVE BEEN LABELED IN THE FIELD TO BE RATED, THE RATING MUST BE MAINTAINED.



A1 FIFTH FLOOR - RENOVATION
SCALE: 1/8" = 1'-0"

N

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-03-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIFTH FLOOR - RENOVATION

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT INTENDED WITHOUT WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A110



D1 GROUND FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL GROUND FLOOR PLAN NOTES:

ON THE GROUND FLOOR, AREA OF WORK SHALL ONLY BE LOCATED IN THE STAIRS. FLOORING SHALL REMAIN AS IS UNLESS OTHERWISE NOTED. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ANY WALL DAMAGED DURING THE RENOVATION WORK. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

GENERAL RCP NOTES:

1. PROVIDE MOISTURE RESISTANT ACT ON CEILING IN ALL TOILET ROOMS.
2. SEE MECHANICAL & ELECTRICAL SHEETS FOR MORE INFORMATION AND LOCATIONS OF LIGHTING AND HVAC SYSTEMS.
3. ANY DISCREPANCIES BETWEEN ARCHITECTURAL & MEP SHEETS SHOULD BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.
4. ALL ACOUSTICAL CEILING SHOWN IN PLANS INDICATE NEW CEILING GRID & TILE. COORDINATE w/ MEP SHEETS.
5. CONTRACTOR SHALL REINSTALL MISCELLANEOUS EQUIPMENT FROM EXISTING CEILING IN NEW CEILING. ADJUST EXISTING FIRE SPRINKLER HEADS TO CENTER OF NEW CEILING TILES. SEE MEP SHEETS FOR ADDITIONAL SCOPE OF WORK.
6. ALL EXISTING AND NEW GYPSUM BOARD CEILINGS IN AREA OF WORK SHALL BE PATCHED AND REPAIRED AND PRIMED AND PAINTED A MINIMUM OF TWO (2) COATS.
7. DEPENDING UPON SEQUENCING OF WINDOW REPLACEMENT WORK, EXTEND NEW CEILING TO EXTERIOR WALLS AFTER THE NEW WALL AND FINISHES ARE INSTALLED.
8. CEILING HEIGHTS IN AREA OF WORK SHALL REMAIN IN SAME LOCATION UNLESS OTHERWISE NOTED.

RCP NOTES

C1	REPLACE EXISTING LIGHTING IN STAIRWELL AS SHOWN ON THE ELECTRICAL DRAWINGS. PATCH AND REPAIR ANY DAMAGED WALL. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
C2	EXISTING CEILING TO REMAIN AS IS. REPLACE EXISTING LIGHTING AND DIFFUSERS AS SHOWN IN THE MECHANICAL AND ELECTRICAL DRAWINGS. PATCH, PRIME AND PAINT CEILING A MINIMUM OF TWO COATS.
C3	EXTEND EXISTING GYPSUM BOARD CEILING TO EDGE OF EXISTING WALL TO ACCOMMODATE NEW MECHANICAL DUCTWORK. PATCH, PRIME AND PAINT CEILING A MINIMUM OF TWO COATS. SEE MECHANICAL DRAWINGS.
C4	INSTALL NEW ACT CEILING AS HIGH AS POSSIBLE. CONTRACTOR TO ACCOMMODATE NEW MECHANICAL AND ELECTRICAL. SEE MECHANICAL AND ELECTRICAL DRAWINGS.



A1 FIRST FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL FIRST FLOOR PLAN NOTES:

ON THE FIRST FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED, EXTEND EXISTING SOFFITS, AND REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. REMOVE AND REPLACE EXISTING CABINETS IN THE AREA OF WORK. INSTALL NEW RADIAL DESK, LECTERN, WITNESS TABLES, REAR TABLES & CHAIR RAIL IN MEETING ROOM. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. INSTALL NEW BULLET RESISTANT MATERIALS TO EAST WALL AS INDICATED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602. COORDINATE AV INSTALLATION w/ OWNER'S VENDOR.

LEGEND

- ACOUSTICAL CEILING TILE (ACT)
- GYPSUM BOARD
- RETURN AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- 2x2 LAY-IN FIXTURE. SEE ELECTRICAL DRAWINGS.
- DECORATIVE WALL SCONCE. SEE ELECTRICAL DRAWINGS.
- 2' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- 4' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- PERIMETER SLOT FIXTURE. SEE ELECTRICAL DRAWINGS.
- SURFACE-MOUNTED LED FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING-MOUNTED FIXTURE. SEE ELECTRICAL DRAWINGS.
- 2" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- 4" ROUND FIXTURE FIXTURE. SEE ELECTRICAL DRAWINGS.
- 6" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING MOUNTED EXIT SIGN
- FIRE SPRINKLER. SEE FIRE PROTECTION DRAWINGS.

A6 RCP LEGEND

SCALE: 1' = 1'-0"

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

GROUND & FIRST FLOOR RCP

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS/ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED WITHOUT WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.

©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A111



D1 SECOND FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL SECOND FLOOR PLAN NOTES:

ON THE SECOND FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

GENERAL RCP NOTES:

1. PROVIDE MOISTURE RESISTANT ACT ON CEILING IN ALL TOILET ROOMS.
2. SEE MECHANICAL & ELECTRICAL SHEETS FOR MORE INFORMATION AND LOCATIONS OF LIGHTING AND HVAC SYSTEMS.
3. ANY DISCREPANCIES BETWEEN ARCHITECTURAL & MEP SHEETS SHOULD BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.
4. ALL ACOUSTICAL CEILING SHOWN IN PLANS INDICATE NEW CEILING GRID & TILE. COORDINATE w/ MEP SHEETS.
5. CONTRACTOR SHALL REINSTALL MISCELLANEOUS EQUIPMENT FROM EXISTING CEILING IN NEW CEILING. ADJUST EXISTING FIRE SPRINKLER HEADS TO CENTER OF NEW CEILING TILES. SEE MEP SHEETS FOR ADDITIONAL SCOPE OF WORK.
6. ALL EXISTING AND NEW GYPSUM BOARD CEILINGS IN AREA OF WORK SHALL BE PATCHED AND REPAIRED AND PRIMED AND PAINTED A MINIMUM OF TWO (2) COATS.
7. DEPENDING UPON SEQUENCING OF WINDOW REPLACEMENT WORK, EXTEND NEW CEILING TO EXTERIOR WALLS AFTER THE NEW WALL AND FINISHES ARE INSTALLED.
8. CEILING HEIGHTS IN AREA OF WORK SHALL REMAIN IN SAME LOCATION UNLESS OTHERWISE NOTED.

RCP NOTES

C1	REPLACE EXISTING LIGHTING IN STAIRWELL AS SHOWN ON THE ELECTRICAL DRAWINGS. PATCH AND REPAIR ANY DAMAGED WALL. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
C2	EXISTING CEILING TO REMAIN AS IS. REPLACE EXISTING LIGHTING AND DIFFUSERS AS SHOWN IN THE MECHANICAL AND ELECTRICAL DRAWINGS. PATCH, PRIME AND PAINT CEILING A MINIMUM OF TWO COATS.
C5	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT IN SAME LOCATION.
C6	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW MOISTURE RESISTANT ACT CEILING IN SAME LOCATION.
C8	REMOVE EXISTING GYPSUM BOARD CEILING AS NECESSARY TO INSTALL NEW MECHANICAL DUCT. PATCH, PRIME AND PAINT CEILING A MINIMUM OF TWO (2) COATS.



A1 THIRD FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL THIRD FLOOR PLAN NOTES:

ON THE THIRD FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

LEGEND

- ACOUSTICAL CEILING TILE (ACT)
- GYPSUM BOARD
- RETURN AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- 2x2 LAY-IN FIXTURE. SEE ELECTRICAL DRAWINGS.
- DECORATIVE WALL SCONCE. SEE ELECTRICAL DRAWINGS.
- 2' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- 4' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- PERIMETER SLOT FIXTURE. SEE ELECTRICAL DRAWINGS.
- SURFACE-MOUNTED LED FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING-MOUNTED FIXTURE. SEE ELECTRICAL DRAWINGS.
- 2" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- 4" ROUND FIXTURE FIXTURE. SEE ELECTRICAL DRAWINGS.
- 6" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING MOUNTED EXIT SIGN
- FIRE SPRINKLER. SEE FIRE PROTECTION DRAWINGS.

A6 RCP LEGEND

SCALE: 1" = 1'-0"

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

SECOND & THIRD FLOOR RCP

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, AND IS AN ARCHITECTURAL WORK PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE SPECIFIC PROJECT FOR WHICH THEY WERE PREPARED WITHOUT THE EXPRESS WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.

©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A112



D1 FOURTH FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL FOURTH FLOOR PLAN NOTES:

ON THE FOURTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEIING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

GENERAL RCP NOTES:

1. PROVIDE MOISTURE RESISTANT ACT ON CEILING IN ALL TOILET ROOMS.
2. SEE MECHANICAL & ELECTRICAL SHEETS FOR MORE INFORMATION AND LOCATIONS OF LIGHTING AND HVAC SYSTEMS.
3. ANY DISCREPANCIES BETWEEN ARCHITECTURAL & MEP SHEETS SHOULD BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.
4. ALL ACOUSTICAL CEILING SHOWN IN PLANS INDICATE NEW CEILING GRID & TILE. COORDINATE w/ MEP SHEETS.
5. CONTRACTOR SHALL REINSTALL MISCELLANEOUS EQUIPMENT FROM EXISTING CEILING IN NEW CEILING. ADJUST EXISTING FIRE SPRINKLER HEADS TO CENTER OF NEW CEILING TILES. SEE MEP SHEETS FOR ADDITIONAL SCOPE OF WORK.
6. ALL EXISTING AND NEW GYPSUM BOARD CEILINGS IN AREA OF WORK SHALL BE PATCHED AND REPAIRED AND PRIMED AND PAINTED A MINIMUM OF TWO (2) COATS.
7. DEPENDING UPON SEQUENCING OF WINDOW REPLACEMENT WORK, EXTEND NEW CEILING TO EXTERIOR WALLS AFTER THE NEW WALL AND FINISHES ARE INSTALLED.
8. CEILING HEIGHTS IN AREA OF WORK SHALL REMAIN IN SAME LOCATION UNLESS OTHERWISE NOTED.

RCP NOTES

C1	REPLACE EXISTING LIGHTING IN STAIRWELL AS SHOWN ON THE ELECTRICAL DRAWINGS. PATCH AND REPAIR ANY DAMAGED WALL. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
C2	EXISTING CEILING TO REMAIN AS IS. REPLACE EXISTING LIGHTING AND DIFFUSERS AS SHOWN IN THE MECHANICAL AND ELECTRICAL DRAWINGS. PATCH, PRIME AND PAINT CEILING A MINIMUM OF TWO COATS.
C5	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT IN SAME LOCATION.
C6	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW MOISTURE RESISTANT ACT CEILING IN SAME LOCATION.
C7	REMOVE EXISTING ACT AS REQUIRED TO INSTALL NEW WINDOW AND FRAMING. EXTEND EXISTING ACT CEILING TO WALL FOLLOWING WINDOW INSTALLATION.



A1 FIFTH FLOOR - RENO RCP

SCALE: 3/32" = 1'-0"

GENERAL FIFTH FLOOR PLAN NOTES:

ON THE FIFTH FLOOR, NEW FLOORING AND BASE SHALL BE INSTALLED AS INDICATED. WHERE EXISTING FLOORING IS NOTED TO BE REMOVED, PREP SUBSTRATE AS RECOMMENDED BY THE MANUFACTURER FOR NEW FLOORING INSTALLATION. REMOVE AND REPLACE EXISTING ACOUSTICAL CEILING (ACT) IN THE AREA OF WORK AS NOTED. PATCH, PRIME, AND PAINT MINIMUM OF TWO COATS ON ALL WALLS THROUGHOUT AND ANY WALL DAMAGED DURING RENOVATION WORK IN THE ADJACENT AREAS. PAINT ANY WALL WHERE TOUCH-UP PAINT IS REQUIRED FLOOR-TO-CEILING AND CORNER-TO-CORNER SO A CONSISTENT FINISH IS ACHIEVED. CLEAN AND TOUCH-UP ALL EXISTING STAINED DOORS. REMOVE, STORE AND REINSTALL ALL EXISTING MONITORS/TV'S IN THE AREA OF WORK. REPLACE EXISTING LIGHTS AS NOTED IN THE ELECTRICAL DRAWINGS. INSTALL NEW LIGHTS AND ACT IN ROOMS THAT HAVE BEEN RECONFIGURED. ADJUST EXISTING SPRINKLER LOCATIONS TO ACCOMMODATE NEW LAYOUT. REMOVE AND REINSTALL EXISTING MISCELLANEOUS DEVICES IN NEW CEILING AS NOTED IN ELECTRICAL SCOPE OF WORK. SEE MECHANICAL SHEET FOR MECHANICAL SCOPE OF WORK. OWNER'S VENDORS SHALL BE INSTALLING NEW FURNITURE AND NEW AV THROUGHOUT THE AREA OF WORK, CONTRACTOR TO COORDINATE AS REQUIRED. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.

LEGEND

- ACOUSTICAL CEILING TILE (ACT)
- GYPSUM BOARD
- RETURN AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL DRAWINGS.
- 2x2 LAY-IN FIXTURE. SEE ELECTRICAL DRAWINGS.
- DECORATIVE WALL SCONCE. SEE ELECTRICAL DRAWINGS.
- 2' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- 4' NARROW LED STRIP. SEE ELECTRICAL DRAWINGS.
- PERIMETER SLOT FIXTURE. SEE ELECTRICAL DRAWINGS.
- SURFACE-MOUNTED LED FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING-MOUNTED FIXTURE. SEE ELECTRICAL DRAWINGS.
- 2" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- 4" ROUND FIXTURE FIXTURE. SEE ELECTRICAL DRAWINGS.
- 6" ROUND FIXTURE. SEE ELECTRICAL DRAWINGS.
- CEILING MOUNTED EXIT SIGN
- FIRE SPRINKLER. SEE FIRE PROTECTION DRAWINGS.

A6 RCP LEGEND

SCALE: 1' = 1'-0"

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH & FIFTH FLOOR RCP

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DOODSTONE ARCHITECTS, AND IS FULLY PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE BENEFIT OF THE OWNER WITHOUT THE WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.

©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A113



D1 GROUND FLOOR
SCALE: 3/32" = 1'-0"



A1 FIRST FLOOR
SCALE: 3/32" = 1'-0"

FINISH ABBREVIATIONS:

C#	= CARPET SELECTION, SEE A602
CT#	= COUNTERTOP SELECTION, SEE A602
ETR	= EXISTING TO REMAIN
L#	= LAMINATE COLOR, SEE A602
LVT#	= LUXURY VINYL TILE SELECTION, SEE A602
P#	= PAINT COLOR, SEE A602
T#	= TILE SELECTION, SEE A602

FINISH LEGEND

LEGEND

- C1: CARPET SELECTION, SEE A602
- C2: CARPET SELECTION, SEE A602
- LVT1 : LVT SELECTION, SEE A602
- T1: TILE SELECTION, SEE A602

E7 FINISH LEGEND

GENERAL FINISH NOTES:

1. PREPARE ALL SUBSTRATES AS RECOMMENDED BY THE MANUFACTURER FOR THE FINAL FINISH PRODUCT.
2. PER NFPA 100, FINISHED FLOOR SURFACE ON BOTH SIDES OF ALL DOORS SHALL NOT VARY BY MORE THAN 1/2" FOR A DISTANCE NOT LESS THAN THE WIDEST DOOR LEAF.
3. PROVIDE ADA COMPLIANT TRANSITION STRIP AT ALL CHANGES IN FLOOR FINISHES.
4. TERMINATE SCHEDULED FLOORING NEATLY AND FLUSH AT BUILT-IN CASEWORK, MILLWORK, OR FIXED FURNITURE BASES UNLESS OTHERWISE NOTED. PROVIDE CLEAN, STRAIGHT EDGE AT TERMINATIONS. FLOORING SHALL EXTEND BENEATH REMOVABLE FURNITURE AND EQUIPMENT.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FINISH PLAN - GROUND & FIRST FLOOR

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A114



D1 SECOND FLOOR

SCALE: 3/32" = 1'-0"



A1 THIRD FLOOR

SCALE: 3/32" = 1'-0"

FINISH ABBREVIATIONS:

C#	= CARPET SELECTION, SEE A602
CT#	= COUNTERTOP SELECTION, SEE A602
ETR	= EXISTING TO REMAIN
L#	= LAMINATE COLOR, SEE A602
LVT#	= LUXURY VINYL TILE SELECTION, SEE A602
P#	= PAINT COLOR, SEE A602
T#	= TILE SELECTION, SEE A602

FINISH LEGEND

LEGEND

- C1: CARPET SELECTION, SEE A602
- C2: CARPET SELECTION, SEE A602
- LVT1 : LVT SELECTION, SEE A602
- T1: TILE SELECTION, SEE A602

E7 FINISH LEGEND

GENERAL FINISH NOTES:

1. PREPARE ALL SUBSTRATES AS RECOMMENDED BY THE MANUFACTURER FOR THE FINAL FINISH PRODUCT.
2. PER NFPA 100, FINISHED FLOOR SURFACE ON BOTH SIDES OF ALL DOORS SHALL NOT VARY BY MORE THAN 1/2" FOR A DISTANCE NOT LESS THAN THE WIDEST DOOR LEAF.
3. PROVIDE ADA COMPLIANT TRANSITION STRIP AT ALL CHANGES IN FLOOR FINISHES.
4. TERMINATE SCHEDULED FLOORING NEATLY AND FLUSH AT BUILT-IN CASEWORK, MILLWORK, OR FIXED FURNITURE BASES UNLESS OTHERWISE NOTED. PROVIDE CLEAN, STRAIGHT EDGE AT TERMINATIONS. FLOORING SHALL EXTEND BENEATH REMOVABLE FURNITURE AND EQUIPMENT.

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FINISH PLAN - SECOND & THIRD FLOOR

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DOODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE OF THIS PROJECT WITHOUT THE CONSENT FROM DOODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A115



D1 FOURTH FLOOR

SCALE: 3/32" = 1'-0"



A1 FIFTH FLOOR

SCALE: 3/32" = 1'-0"

FINISH ABBREVIATIONS:

C#	= CARPET SELECTION, SEE A602
CT#	= COUNTERTOP SELECTION, SEE A602
ETR	= EXISTING TO REMAIN
L#	= LAMINATE COLOR, SEE A602
LVT#	= LUXURY VINYL TILE SELECTION, SEE A602
P#	= PAINT COLOR, SEE A602
T#	= TILE SELECTION, SEE A602

FINISH LEGEND

LEGEND

- C1: CARPET SELECTION, SEE A602
- C2: CARPET SELECTION, SEE A602
- LVT1 : LVT SELECTION, SEE A602
- T1: TILE SELECTION, SEE A602

E7 FINISH LEGEND

GENERAL FINISH NOTES:

1. PREPARE ALL SUBSTRATES AS RECOMMENDED BY THE MANUFACTURER FOR THE FINAL FINISH PRODUCT.
2. PER NFPA 100, FINISHED FLOOR SURFACE ON BOTH SIDES OF ALL DOORS SHALL NOT VARY BY MORE THAN 1/2" FOR A DISTANCE NOT LESS THAN THE WIDEST DOOR LEAF.
3. PROVIDE ADA COMPLIANT TRANSITION STRIP AT ALL CHANGES IN FLOOR FINISHES.
4. TERMINATE SCHEDULED FLOORING NEATLY AND FLUSH AT BUILT-IN CASEWORK, MILLWORK, OR FIXED FURNITURE BASES UNLESS OTHERWISE NOTED. PROVIDE CLEAN, STRAIGHT EDGE AT TERMINATIONS. FLOORING SHALL EXTEND BENEATH REMOVABLE FURNITURE AND EQUIPMENT.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FINISH PLAN - FOURTH & FIFTH FLOOR

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DOODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE OF THIS PROJECT WITHOUT THE CONSENT FROM DOODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A116



D1 THIRD FLOOR MEN'S RR - DEMO
SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.

E5 VIEW OF LAVATORIES

E6 VIEW OF LAVATORIES

D5 VIEW FROM ENTRY

D6 VIEW OF STALLS



A1 THIRD FLOOR MEN'S RR - RENO
SCALE: 3/8" = 1'-0"

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.
N-9	INSTALL NEW TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.

GENERAL ENLARGED PLAN COMMENTS:
1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE
SCALE: 1' = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

THIRD FLOOR ENLARGED - MEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DOODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE INTENDED BY DODSTONE ARCHITECTS, INC. WITHOUT THE EXPRESS CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A401



D1 THIRD FLOOR WOMEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.



A1 THIRD FLOOR WOMEN'S RR - RENO

SCALE: 3/8" = 1'-0"

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.
N-9	INSTALL NEW TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.

E5 VIEW FROM ENTRY

E6 VIEW OF LAVATORIES

D5 VIEW OF STALLS

D6 VIEW OF HC STALL

GENERAL ENLARGED PLAN COMMENTS:

1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

THIRD FLOOR ENLARGED - WOMEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE INTENDED WITHOUT THE WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A402



D1 FOURTH FLOOR MEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.

E5 VIEW OF LAVATORIES

E6 VIEW OF STALLS

D5 VIEW OF ADA STALL

D6 VIEW OF URINALS



A1 FOURTH FLOOR MEN'S RR - RENO

SCALE: 3/8" = 1'-0"

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.
N-9	INSTALL NEW TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.

GENERAL ENLARGED PLAN COMMENTS:

1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH FLOOR ENLARGED - MEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE INTENDED WITHOUT THE WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A403



D1 FOURTH FLOOR WOMEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.



E5 VIEW OF STALLS

E6 VIEW FROM ENTRY

D5 VIEW OF LAVATORIES

D6 VIEW OF HC STALL

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.



A1 FOURTH FLOOR WOMEN'S RR - RENO

SCALE: 3/8" = 1'-0"

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.
N-9	INSTALL NEW TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.

GENERAL ENLARGED PLAN COMMENTS:

1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH FLOOR ENLARGED - WOMEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT SPECIFICALLY INTENDED IS PROHIBITED WITHOUT THE EXPRESS WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A404



D1 FOURTH FLOOR RR - DEMO

SCALE: 3/8" = 1'-0"



D2 FOURTH FLOOR RR - RENO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES

D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-10	REMOVE AND SALVAGE EXISTING MIRROR. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.

ENLARGED FLOOR PLAN KEYNOTES

N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-4	REINSTALL SALVAGED MIRROR ABOVE NEW LAVATORY.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.

GENERAL ENLARGED PLAN COMMENTS:

1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A1 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

GENERAL INTERIOR ELEVATION NOTES:

1. SEE A1/LS001 FOR MOUNTING HEIGHTS.
2. SEE SHEET #LayID(ref) FOR MILLWORK DETAILS.
3. ALL DOORS AS SCHEDULED ON A601.
4. SEE A51A401FOR BATHROOM ACCESSORY SCHEDULE.
5. WALL MOUNTED DEVICES, SWITCH PLATES AND OUTLETS NOT SHOWN FOR CLARITY. (SEE MEP)
6. INTERIOR FINISHES PER FINISH SCHEDULE ON SHEET A602.

D3 VIEW OF LAV & TOILET

C3 VIEW OF LAV & TOILET

B3 VIEW OF LAV & TOILET

A3 VIEW OF LAV & TOILET



E5 430A RR - N

SCALE: 1/2" = 1'-0"



E6 430A RR - E

SCALE: 1/2" = 1'-0"



D5 430A RR - S

SCALE: 1/2" = 1'-0"



D6 430A RR - W

SCALE: 1/2" = 1'-0"



B5 430B RR - N

SCALE: 1/2" = 1'-0"



B6 430B RR - E

SCALE: 1/2" = 1'-0"



A5 430B RR - S

SCALE: 1/2" = 1'-0"



A6 430B RR - W

SCALE: 1/2" = 1'-0"

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FOURTH FLOOR ENLARGED - RESTROOMS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PERFORMANCE OF THE CONTRACT WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2026 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A405



D1 FIFTH FLOOR MEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.

E5 VIEW OF HC STALL

E6 VIEW OF LAVATORIES

D5 VIEW FROM ENTRY

D6 VIEW OF URINALS



D1 FIFTH FLOOR MEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.
N-9	INSTALL NEW TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.

GENERAL ENLARGED PLAN COMMENTS:
1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

A1 FIFTH FLOOR MEN'S RR - RENO

SCALE: 3/8" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIFTH FLOOR ENLARGED - MEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE INTENDED IS PROHIBITED WITHOUT CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A406



D1 FIFTH FLOOR WOMEN'S RR - DEMO

SCALE: 3/8" = 1'-0"

DEMO ENLARGED PLAN KEYNOTES	
D-1	REMOVE EXISTING FLOORING AND BASE THROUGHOUT. PREP FLOOR TO RECEIVE FINAL FINISHES.
D-2	REMOVE THE EXISTING GYPSUM BOARD THROUGHOUT THE ROOM. PREP AREA TO RECEIVE TILE BACKER BOARD AND WALL TILE.
D-3	REMOVE THE EXISTING TOILET ACCESSORIES IN THE ROOM. INFILL WALL WHERE ACCESSORIES ARE RECESSED. INFILL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-4	REMOVE ALL EXISTING TOILET PARTITIONS AND DOORS WITHIN ROOM ALONG w/ ALL HARDWARE AND ATTACHMENT DEVICES.
D-5	REMOVE EXISTING COUNTERTOP AND LAVATORIES AND ALL ASSOCIATED ATTACHMENT DEVICES.
D-6	REMOVE EXISTING SHELF AND ALL ATTACHMENT DEVICES.
D-7	REMOVE EXISTING TOILET FIXTURES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. INSTALL NEW PLUMBING FIXTURES IN ONE-FOR-ONE REPLACEMENT. SEE PLUMBING DRAWINGS.
D-8	REMOVE EXISTING WALL MOUNTED SINK. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D-9	REMOVE EXISTING WALL MOUNTED GRAB BARS.
D-11	REMOVE EXISTING GYPSUM BOARD CEILING AND INSTALL NEW ACT AT SAME CEILING HEIGHT. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.

E5 VIEW FROM ENTRY

E6 VIEW OF LAVATORIES

D5 VIEW OF STALLS

D6 VIEW OF LAVATORIES



A1 FIFTH FLOOR WOMEN'S RR - RENO

SCALE: 3/8" = 1'-0"

NOTE:
PER FBC-BC 1210.3.2, WALLS OR PARTITIONS SHALL BEGIN AT A HEIGHT NOT MORE THAN 12 INCHES (305 MM) FROM AND EXTEND NOT LESS THAN 60 INCHES (1524 MM) ABOVE THE FINISHED FLOOR SURFACE. THE WALLS OR PARTITIONS SHALL EXTEND FROM THE WALL SURFACE AT EACH SIDE OF THE URINAL NOT LESS THAN 18 INCHES (457 MM) OR TO A POINT NOT LESS THAN 6 INCHES (152 MM) BEYOND THE OUTERMOST FRONT LIP OF THE URINAL MEASURED FROM THE FINISHED BACKWALL SURFACE, WHICHEVER IS GREATER.

ENLARGED FLOOR PLAN KEYNOTES	
N-1	INSTALL TILE BACKER BOARD ON ALL WALL IN PREPARATION FOR NEW TILE.
N-2	INSTALL NEW ADA COMPLIANT TOILET FIXTURE IN EXISTING LOCATION. PROVIDE ALL NECESSARY VALVES/ CONNECTIONS/HANGERS FOR A COMPLETE, CODE COMPLIANT, AND WATER TIGHT CONNECTION. SEE PLUMBING DRAWINGS. PATCH WALL AND FLOOR TO MATCH ADJACENT CONSTRUCTION AND PREP AS REQUIRED TO RECEIVE SCHEDULED FINISHES.
N-3	INSTALL NEW MILLWORK AND ALL ASSOCIATED ATTACHMENT DEVICES. SEE DETAILS.
N-5	INSTALL NEW VANITY AND UNDERMOUNT SINKS. SEE DETAIL C5/A412.
N-6	INSTALL NEW TOILET PARTITONS AS SHOWN.
N-7	INSTALL NEW TILE FLOOR AND BASE IN RESTROOM ENTRY. PATCH AND REPAIR EXISTING GYP. BD. WALLS AND PRIME AND PAINT A MINIMUM OF TWO (2) COATS.
N-8	INSTALL NEW TILE FLOOR, BASE AND WALL TILE IN RESTROOMS AS PER MANUFACTURER'S RECOMMENDATION.

GENERAL ENLARGED PLAN COMMENTS:
1. PROVIDE BLOCKING AS REQUIRED TO SECURELY SUPPORT ALL RESTROOM ACCESSORIES.
2. ALL RESTROOM ACCESSORIES MUST BE INSTALLED SO THEY ARE ADA COMPLIANT. ELEVATIONS INDICATE PREFERRED MOUNTING LOCATION.
3. THE ADA CODE HAS CONSTRUCTION TOLERANCE BUILT INTO THE CODE. IF ADJUSTMENTS FROM THE DIMENSIONS SHOWN ARE NECESSARY, CONTRACTOR IS TO VERIFY THAT ALL ADA GUIDELINES ARE STILL FOLLOWED.
4. SEE A1/LS001 FOR MOUNTING HEIGHTS.
5. FOR FINISHES, SEE FINISH SCHEDULES ON SHEET A602.
6. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE PER FBC 1210.2.2.
7. ALL PLUMBING FIXTURES IN AREA OF WORK TO BE REMOVED AND REPLACED IN KIND. SEE MEP DRAWINGS.
8. REMOVE ALL ITEMS HANGING ON WALLS WITHIN THE AREA OF WORK. TURN OVER TO THE OWNER FOR THEIR REUSE. REPLACE ANY ITEMS DAMAGED DURING DEMOLITION OR CONSTRUCTION ACTIVITIES TO MATCH EXISTING. REPAIR ANY RESULTING VOIDS IN ANY EXISTING WALLS TO REMAIN. FINISH TO MATCH ADJACENT SURFACES.

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

TAG	DESCRIPTION	MFR.	MODEL	NOTE
C1	TOILET SEAT COVER DISPENSER	AJW	U851	SURFACE MOUNTED TOILET SEAT COVER DISPOSAL. INSTALL SO TOP OF UNIT IS 4'-6" A.F.F.
G36	36" LONG GRAB BAR	AJW	UG3-A36	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
G42	42" LONG GRAB BAR	AJW	UG3-A42	1-1/2" DIAMETER SS GRAB BAR w/ EXPOSED FLANGE. PROVIDE BLOCKING IN WALL AS RECOMMENDED BY THE MANUFACTURER AND AS REQUIRED SO BARS CAN RESIST A MINIMUM OF 250 LBS. EXERTED HORIZONTALLY OR VERTICALLY. INSTALL SO CENTERLINE IS 34.5" A.F.F.
H1	COAT HOOK	AJW	UB16	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. TOP OF HOOK MUST NOT BE MORE THAN 48" A.F.F.
M1	18" X 36" MIRROR	AJW	U700 SERIES	SURFACE MOUNTED MIRROR w/ STAINLESS STEEL FRAME. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
M2	22" X 36" MIRROR			SURFACE MOUNTED MIRROR w/ 2" ETCHED BAND EA. SIDE. INSTALL SO REFLECTIVE SURFACE (NOT BOTTOM EDGE OF FRAME) IS NO MORE THAN 40" A.F.F.
N1	SANITARY NAPKIN DISPOSAL	AJW	U591	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL. INSTALL SO TOP OF UNIT IS 2'-5" A.F.F.
P1	PAPER TOWEL DISPENSER	AJW	U180	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. ACCESS POINT MUST NOT BE MORE THAN 48" A.F.F.
R1	WASTE RECEPTACLE	BOBRICK	B-2400	WASTE RECEPTACLE. INSTALL AS SHOWN IN THE PLANS.
S1	SOAP DISPENSER	AJW	U125	SURFACE MOUNT AS RECOMMENDED BY MANUFACTURER AND AS REQUIRED FOR ADA COMPLIANCE. CENTERLINE OF OPERATOR MUST NOT BE MORE THAN 48" A.F.F.
T1	TOILET TISSUE DISPENSER	AJW	U840	SURFACE MOUNTED STANDARD ROLL TOILET PAPER DISPENSER. INSTALL SO CENTERLINE OF SPINDLE IS 1'-9" A.F.F.

A5 ACCESSORY SCHEDULE

SCALE: 1' = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FIFTH FLOOR ENLARGED - WOMEN'S RESTROOM

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT SPECIFIED HEREIN WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A407



E1 301 WOMEN - N

SCALE: 1/2" = 1'-0"



E5 301 WOMEN - E

SCALE: 1/2" = 1'-0"



D1 301 WOMEN - S

SCALE: 1/2" = 1'-0"



D5 301 WOMEN - W

SCALE: 1/2" = 1'-0"



B1 302 MEN - N

SCALE: 1/2" = 1'-0"



B4 302 MEN - E

SCALE: 1/2" = 1'-0"



A1 302 MEN - S

SCALE: 1/2" = 1'-0"



A4 302 MEN - W

SCALE: 1/2" = 1'-0"

NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

GENERAL INTERIOR ELEVATION NOTES:

1. SEE A1/LS001 FOR MOUNTING HEIGHTS.
2. SEE SHEET #LayID(ref) FOR MILLWORK DETAILS.
3. ALL DOORS AS SCHEDULED ON A601.
4. SEE A51A401FOR BATHROOM ACCESSORY SCHEDULE.
5. WALL MOUNTED DEVICES, SWITCH PLATES AND OUTLETS NOT SHOWN FOR CLARITY. (SEE MEP)
6. INTERIOR FINISHES PER FINISH SCHEDULE ON SHEET A602.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

SUBMISSION TITLE	DATE
SCHEMATIC DESIGN	06/12/25
100% CONSTRUCTION DOCUMENTS	10/09/25
100% PERMIT DOCUMENTS	10/31/25

#	REVISION TITLE	DATE

RESTROOM INTERIOR ELEVATIONS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS SUBJECT TO PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE FOR WHICH THEY WERE PREPARED IS PROHIBITED WITHOUT THE EXPRESS WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A408



E1 402 MEN - N

SCALE: 1/2" = 1'-0"



E5 401 WOMEN - E

SCALE: 1/2" = 1'-0"



D1 400B E. HALL - S

SCALE: 1/2" = 1'-0"



D5 400B E. HALL - W

SCALE: 1/2" = 1'-0"



B1 401 WOMEN - N

SCALE: 1/2" = 1'-0"



B5 402 MEN - E

SCALE: 1/2" = 1'-0"



A1 402 MEN - S

SCALE: 1/2" = 1'-0"



A5 402 MEN - W

SCALE: 1/2" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	REVISION TITLE

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

RESTROOM INTERIOR ELEVATIONS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND SHALL BE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT SPECIFICALLY INTENDED WITHOUT CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A409



E1 501 WOMEN - N

SCALE: 1/2" = 1'-0"



D1 501 WOMEN - S

SCALE: 1/2" = 1'-0"



B1 502 MEN - N

SCALE: 1/2" = 1'-0"



A1 502 MEN - S

SCALE: 1/2" = 1'-0"

E5 501 WOMEN - E

SCALE: 1/2" = 1'-0"



D5 501 WOMEN - W

SCALE: 1/2" = 1'-0"



B4 502 MEN - E

SCALE: 1/2" = 1'-0"



A4 502 MEN - W

SCALE: 1/2" = 1'-0"



NOTE:
DIMENSIONS FOR PLACEMENT OF ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH. DIMENSIONS FOR PLACEMENT OF INTERIOR WALLS ARE TAKEN TO FACE OF STUDS.

GENERAL INTERIOR ELEVATION NOTES:

1. SEE A1/LS001 FOR MOUNTING HEIGHTS.
2. SEE SHEET #LayID(ref) FOR MILLWORK DETAILS.
3. ALL DOORS AS SCHEDULED ON A601.
4. SEE A51A401FOR BATHROOM ACCESSORY SCHEDULE.
5. WALL MOUNTED DEVICES, SWITCH PLATES AND OUTLETS NOT SHOWN FOR CLARITY. (SEE MEP)
6. INTERIOR FINISHES PER FINISH SCHEDULE ON SHEET A602.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	08/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

RESTROOM INTERIOR ELEVATIONS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE FOR WHICH THEY WERE PREPARED WITHOUT PRIOR WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A410



D1 FIRST FLOOR RENO
SCALE: 3/8" = 1'-0"

D2 SECOND FLOOR RENO
SCALE: 3/8" = 1'-0"

NOTE:
DIMENSIONS FOR STUD WALLS ARE TAKEN TO FACE OF STUDS. DIMENSIONS FOR ACCESSORIES, PLUMBING FIXTURES & TOILET PARTITIONS ARE TAKEN FROM FACE OF WALL FINISH.

CABINETRY ABBREVIATIONS:
B = BASE CABINET
BD = BASE CABINET W/ DRAWER
C = CUSTOM CABINET
CB = CORNER BASE
CT = COUNTER TOP
D = DRAWER BASE
DW = DISHWASHER W/ COUNTER TOP
SB = SINK BASE
T = TALL CABINET
W = WALL CABINET
# = WIDTH OF CABINET IN INCHES

GENERAL INTERIOR ELEVATION NOTES:
1. SEE A1/LS001 FOR MOUNTING HEIGHTS.
2. SEE SHEET A412 FOR MILLWORK DETAILS.
3. ALL DOORS AS SCHEDULED ON A601.
4. SEE A51A401FOR BATHROOM ACCESSORY SCHEDULE.
5. WALL MOUNTED DEVICES, SWITCH PLATES AND OUTLETS NOT SHOWN FOR CLARITY. (SEE MEP)
6. INTERIOR FINISHES PER FINISH SCHEDULE ON SHEET A602.

GENERAL CABINET NOTES:
1. ALL TOE KICKS TO BE LAMINATED AND/OR MATCH THE SCHEDULED BASE IN THE ROOM (AT GC'S DISCRETION.)
2. PROVIDE FILLER PANELS AS NEEDED.
3. FIELD VERIFY AREAS PRIOR TO CONSTRUCTING CABINETRY.
4. COORDINATE FINAL OPENING SIZES W/ CONTRACTOR.
5. ALL EXPOSED SURFACES SHOULD BE LAMINATED UNLESS NOTED OTHERWISE.
6. PROVIDE BLOCKING AS REQUIRED TO SUPPORT WALL CABINETS.
7. VERIFY THAT ALL PROPOSED APPLIANCES WILL FIT INTO CABINETRY AS SHOWN.
   a. CABINETS SHOULD BE CUSTOM SIZED TO FIT OVEN AND/OR MICROWAVES. PROVIDE HOOKUPS TO THESE APPLIANCES AS NEEDED. MICROWAVES SHOULD BE ON A SEPARATE CIRCUIT.
   b.34" COUNTER TOP HEIGHT IS AN ADA REQUIREMENT. VERIFY THAT DISH WASHER WILL BE ABLE TO FIT BELOW AS SHOWN.

ID	DESCRIPTION	MFR.	MODEL	NOTE	MISCELLANEOUS INSTRUCTIONS
C2	COFFEE MAKER w/ 3 LOWER WARMERS.	BUNN	AXIOM-DV-3 38700.0009	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
C1	COFFEE MAKER w/ 2 UPPER & 1 LOWER WARMER	BUNN	AXIOM-15-3 38700.0000	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
F1	UNDERCOUNTER SOLID DOOR REFRIGERATOR	TRUE MANUFACTURING	TUC-24-HC	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
F2	REACH- IN SOLID SWING DOOR REFRIGERATOR	TRUE MANUFACTURING	T-12-HC	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
IM	UNDERCOUNTER ICE MACHINE w/ BUILT-IN STORAGE BIN	HOSHIZAKI	C-80BAJ-(AD)DS	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
IMW	ICE MACHINE AND WATER DISPENSER	HOSHIZAKI	DCM-271BAH	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PROVIDE NECESSARY POWER AND WATER CONNECTIONS. PUT ON A DEDICATED CIRCUIT.
M	COUNTERTOP MICROWAVE	WHIRLPOOL	WMH53521H	TO BE PROVIDED AND INSTALLED BY THE CONTRACTOR.	PUT ON DEDICATED CIRCUIT. PROVIDE POWER OUTLET FOR MICROWAVE AT TWO LOCATIONS: ONE, ABOVE THE COUNTER TO THE RIGHT OF THE SINK (FOR ADA COMPLIANCE), AND TWO, AT THE REAR OF THE OPEN SHELF.

E4 APPLICANCE SCHEDULE
SCALE: 1' = 1'-0"



D4 215C BREAK - W
SCALE: 1/2" = 1'-0"



D6 117 MEETING RM - N
SCALE: 1/2" = 1'-0"





A1 SECOND FLOOR RENO
SCALE: 3/8" = 1'-0"

B4 227A WORK RM - E
SCALE: 1/2" = 1'-0"



A3 227B BREAK - S
SCALE: 1/2" = 1'-0"

A5 227B BREAK - W
SCALE: 1/2" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

ENLARGED PLAN & INTERIOR ELEVATIONS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT SPECIFICALLY AUTHORIZED BY DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A411



C1 TALL CABINET @ RESTROOMS

SCALE: 1 1/2"= 1'-0"



C2 BASE CABINET @ RR

SCALE: 1 1/2"= 1'-0"



C4 WALL CABINET

SCALE: 1 1/2"= 1'-0"



C5 ADA SINK COUNTER DETAIL

SCALE: 1 1/2"= 1'-0"



A1 BASE CABINET w/ DRAWER

SCALE: 1 1/2"= 1'-0"



A2 BASE CABINET

SCALE: 1 1/2"= 1'-0"



A4 SINK BASE CABINET

SCALE: 1 1/2"= 1'-0"



A5 COUNTERTOP DETAIL

SCALE: 1 1/2"= 1'-0"

NOTE: DECORATIVE CABINET HARDWARE SHALL MATCH PULLS LOCATED ELSEWHERE IN THE BUILDING.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	09/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

MILLWORK DETAILS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PERFORMANCE OF WORK WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A412



E1 DECK FRONT ELEVATION
SCALE: 3/4" = 1'-0"



E2 DESK PLAN
SCALE: 3/4" = 1'-0"

NOTE: CONTRACTOR TO SUBMIT DETAILED SHOP DRAWINGS FOR OWNER REVIEW. COORDINATE AV REQUIREMENTS w/ OWNERS AV SUBCONTRACTORS

NOTE: MEETING RM 117 DAIS, DESK, LECTERN, AND WITNESS TABLE FINISH AND PROFILES SHALL MATCH EXISTING DESKS LOCATED IN MEETING RM 412



E4 WITNESS AND LECTERN PLAN
SCALE: 3/4" = 1'-0"



C1 DESK SIDE ELEVATION
SCALE: 1 1/2"= 1'-0"



C2 DESK SECTION
SCALE: 1 1/2"= 1'-0"



C4 WITNESS AND LECTERN REAR ELEVATION
SCALE: 3/4" = 1'-0"



A1 LECTERN SIDE ELEVATION
SCALE: 1 1/2"= 1'-0"



A2 LECTERN SECTION
SCALE: 1 1/2"= 1'-0"



A4 WITNESS AND LECTERN FRONT ELEVATION
SCALE: 3/4" = 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE
KNOTT BUILDING
INTERIOR RENOVATIONS
PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

LECTERN & WITNESS TABLE

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS FULLY PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED BY DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A413



NOTE: MEETING RM 117 DAIS, DESK, LECTERN, AND WITNESS TABLE FINISH AND PROFILES SHALL MATCH EXISTING DESKS LOCATED IN MEETING RM 412

NOTE: CONTRACTOR TO SUBMIT DETAILED SHOP DRAWINGS FOR OWNER REVIEW. COORDINATE AV REQUIREMENTS w/ OWNERS AV SUBCONTRACTORS

E1 117 COMMITTEE MEETING RM - E
SCALE: 1/2" = 1'-0"



E6 CHAIR RAIL DETAIL
SCALE: 3" = 1'-0"



A1 FIRST FLOOR RENO - MEETING ROOM 117
SCALE: 1/4" = 1'-0"



C4 MEETING RM DESK REAR ELEVATION
SCALE: 3/4" = 1'-0"



A4 MEETING RM DESK DETAIL
SCALE: 1 1/2"= 1'-0"



C6 KNEE WALL DOOR ELEVATION
SCALE: 3/4" = 1'-0"



A6 KNEE WALL DOOR SECTION
SCALE: 1 1/2"= 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

MEETING RM 117

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS SOLELY PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE SPECIFIC PROJECT INTENDED WITHOUT WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A414



E1 CORNER TRIM @ TILE
SCALE: 1 1/2"= 1'-0"



D1 WOOD BASE @ FLOOR
SCALE: 3" = 1'-0"



C1 RUBBER BASE @ FLOOR
SCALE: 3" = 1'-0"



B1 CARPET BASE @ FLOOR
SCALE: 3" = 1'-0"



A1 TILE @ FLOOR
SCALE: 3" = 1'-0"



E2 TYPICAL NARROW BULKHEAD
SCALE: 3" = 1'-0"



C2 TYPICAL BULKHEAD
SCALE: 3" = 1'-0"



A2 DIGITAL SIGN DETAIL
SCALE: 1 1/2"= 1'-0"



D4 TYPICAL SOUND WALL
SCALE: 1 1/2"= 1'-0"



D6 TYPICAL GYPSUM WALL
SCALE: 1 1/2"= 1'-0"



A4 TYPICAL SOUND WALL @ EXISTING WALL
SCALE: 1 1/2"= 1'-0"



A6 BULLET RESISTANT WALL
SCALE: 1 1/2"= 1'-0"

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

WALL & FLOOR DETAILS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PURPOSE FOR WHICH THEY WERE PREPARED WITHOUT PRIOR WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A501



D15



D9

D15

D9

E1 MEETING RM 117

E2 MEETING RM 117

E3 MEETING RM 117

E4 MEETING RM 117

FIRST FLOOR

D8



D15

D11

D15

D16

D9

D15

D16

C1 E. HALL 200A

C2 E. HALL 200A

C3 WORK RM 227

C4 CONF. 215B

SECOND FLOOR

D8

D15

D9

D9

D9

D15

A1 HALL 330D

A2 RECEPTION 335 (DEMO)

A3 OFFICE 320B

A4 OFFICE 325F (DEMO)

THIRD FLOOR

DEMO PLAN KEYNOTES

D1	REMOVE EDGE OF EXISTING GYPSUM BOARD SOFFIT AND PREP AS REQUIRED TO EXTEND SOFFIT TO ACCOMMODATE NEW DUCTWORK.
D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING, INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D7	REMOVE AND SALVAGE EXISTING DOOR FRAME. INFILL OPENING WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D8	REMOVE EXISTING TACK BOARD TO BE REPLACED WITH DIGITAL BOARDS AND PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DIGITAL BOARD AND ASSOCIATED BLOCKING. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D10	CONTRACTOR TO REMOVE EXISTING CABINETS, COUNTERS AND SHELVING AND ALL ASSOCIATED ATTACHMENT DEVICES.
D11	REMOVE WOOD TRIM AND SHELVING IN ALCOVE AND INFILL WALL NICHE.
D12	REMOVE AND SALVAGE EXISTING BLINDS FOR INSTALLATION IN NEW WINDOWS.
D13	REMOVE EXISTING CABINETRY AND APPLIANCES FOR INSTALLATION OF NEW WINDOWS. REMOVE EXISTING FINISHES IN THE ROOM AND PREP SURFACES FOR NEW FINISH INSTALLATION. SEE FINISH SCHEDULE.
D14	REMOVE EXISTING RAMP AND HANDRAIL AS NEEDED FOR INSTALLATION OF NEW WINDOWS AND STRUCTURAL SUPPORT. CONTRACTOR TO SALVAGE EXISTING HANDRAIL AND BASE TO REINSTALL AFTER WINDOW IS REPLACED IN SEPARATE WINDOW REPLACEMENT PROJECT. REMOVE EXISTING CARPET AND INSTALL NEW. ADJUST CEILINGS AS NECESSARY TO COMPLETE WINDOW AND SUPPORT FRAME INSTALLATION. REINSTALL RAMP AND FINISHES TO MATCH EXISTING.
D15	REMOVE EXISTING WALL BASE AND CARPET IN ROOM. PREP FLOOR IN ACCORDANCE TO MANUFACTUER'S RECOMMENDATION TO ACCEPT NEW FLOORING. SEE FINISH SCHEDULE.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.
D17	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. DOOR SHALL STAY IN SAME LOCATION, FLIP DOOR SWING AND INSTALL NEW HARDWARE.
D18	REMOVE EXISTING TACK BOARD AND INSTALL NEW DIGITAL SIGN AT NEW DOOR LOCATION.
D19	CONTRACTOR TO REMOVE EXISTING GLASS AND ITEMS IN DISPLAY CASE AND TURN OVER ITEMS TO OWNER'S REPRESENTATIVE. REMOVE EXISTING WOOD SILL FOR NEW SOLID SURFACE. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.

Dodstone Architects

3011-1 Powell Road
Tallahassee, FL 32308

850.656.7326

JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

EXISTING PHOTOS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND SPECIFICATIONS, AND ALL SUCH PROJECTED BY ARCHITECTS, AND AS SUCH ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT INTENDED HEREIN WITHOUT WRITTEN CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.

©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A502



E1 MEETING RM 412C



E2 CORRIDOR 426

E3 BREAK ROOM 430D

E4 BREAK ROOM 430D

FOURTH FLOOR

C1 OFFICE 525E

C2 WORK RM 537

C3 W. HALL 500C

C4 RECEPTION 530 (DEMO)

FIFTH FLOOR



A1 WINDOW JAMB



A2 WINDOW SILL

A3 @ CEILING

EXISTING EXTERIOR WALL

DEMO PLAN KEYNOTES

D1	REMOVE EDGE OF EXISTING GYPSUM BOARD SOFFIT AND PREP AS REQUIRED TO EXTEND SOFFIT TO ACCOMMODATE NEW DUCTWORK.
D2	REMOVE THE EXISTING GYPSUM BOARD AND METAL STUDS AT THE EXTERIOR WALL FROM CORNER TO CORNER FOR INSTALLATION OF NEW WINDOWS, STRUCTURAL SUPPORT, FLASHING AND WATERPROOFING UNDER SEPARATE PROJECT. INSTALL NEW INTERIOR STUD WALL IN SAME LOCATION w/ METAL STUDS TO MATCH EXISTING, INSULATION TO MATCH EXISTING AND 5/8" TYPE 'X' GYPSUM BOARD AND ASSOCIATED FINISHES AS SCHEDULED. PATCH AND REPAIR ANY DAMAGES TO WALL AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. ADJUST CEILING AND FLOORING TO ACCOMMODATE NEW WALL INSTALLATION.
D3	REMOVE EXISTING WALL TO ACCOMMODATE NEW CONSTRUCTION. PATCH AND REPAIR ANY DAMAGES TO WALLS AND FINISHES IF NECESSARY. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES. PRIME AND PAINT TWO COATS.
D4	REMOVE EXISTING SECTION OF WALL AND ASSOCIATED DOOR TO ACCOMMODATE NEW CONSTRUCTION. SALVAGE EXISTING DOOR FOR INSTALLATION IN NEW LOCATION. PATCH AND REPAIR ANY DAMAGES TO MATCH ADJACENT SURFACES.
D5	REMOVE EXISTING SECTION OF WALL AS REQUIRED FOR NEW DOOR INSTALLATION. SEE DOOR SCHEDULE ON A601. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D6	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. INFILL WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES.
D7	REMOVE AND SALVAGE EXISTING DOOR FRAME. INFILL OPENING WITH NEW WALL TO MATCH ADJACENT WALL CONSTRUCTION. PREP WALL AS REQUIRED TO RECEIVE FINAL FINISHES. REPAIR ANY RESULTING DAMAGE OR VOIDS TO MATCH ADJACENT SURFACES.
D8	REMOVE EXISTING TACK BOARD TO BE REPLACED WITH DIGITAL BOARDS AND PORTION OF EXISTING WALL FOR INSTALLATION OF NEW DIGITAL BOARD AND ASSOCIATED BLOCKING. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.
D9	REMOVE EXISTING WINDOW SILL FOR INSTALLATION OF NEW WINDOW AND INSTALL NEW WINDOW SILL. NEW WINDOWS WILL BE REPLACED IN A SEPARATE WINDOW REPLACEMENT PROJECT UNDER A SEPARATE PERMIT.
D10	CONTRACTOR TO REMOVE EXISTING CABINETS, COUNTERS AND SHELVING AND ALL ASSOCIATED ATTACHMENT DEVICES.
D11	REMOVE WOOD TRIM AND SHELVING IN ALCOVE AND INFILL WALL NICHE.
D12	REMOVE AND SALVAGE EXISTING BLINDS FOR INSTALLATION IN NEW WINDOWS.
D13	REMOVE EXISTING CABINETRY AND APPLIANCES FOR INSTALLATION OF NEW WINDOWS. REMOVE EXISTING FINISHES IN THE ROOM AND PREP SURFACES FOR NEW FINISH INSTALLATION. SEE FINISH SCHEDULE.
D14	REMOVE EXISTING RAMP AND HANDRAIL AS NEEDED FOR INSTALLATION OF NEW WINDOWS AND STRUCTURAL SUPPORT. CONTRACTOR TO SALVAGE EXISTING HANDRAIL AND BASE TO REINSTALL AFTER WINDOW IS REPLACED IN SEPARATE WINDOW REPLACEMENT PROJECT. REMOVE EXISTING CARPET AND INSTALL NEW. ADJUST CEILINGS AS NECESSARY TO COMPLETE WINDOW AND SUPPORT FRAME INSTALLATION. REINSTALL RAMP AND FINISHES TO MATCH EXISTING.
D15	REMOVE EXISTING WALL BASE AND CARPET IN ROOM. PREP FLOOR IN ACCORDANCE TO MANUFACTUER'S RECOMMENDATION TO ACCEPT NEW FLOORING. SEE FINISH SCHEDULE.
D16	CONTRACTOR SHALL REMOVE GYPSUM BOARD FROM ONE SIDE OF WALL AND EXTEND STUDS AND GYPSUM BOARD ON BOTH SIDES OF THE WALL TO UNDERSIDE OF DECK ABOVE. INSTALL ACOUSTICAL INSULATION FLOOR TO DECK.
D17	REMOVE AND SALVAGE EXISTING DOOR AND FRAME. DOOR SHALL STAY IN SAME LOCATION, FLIP DOOR SWING AND INSTALL NEW HARDWARE.
D18	REMOVE EXISTING TACK BOARD AND INSTALL NEW DIGITAL SIGN AT NEW DOOR LOCATION.
D19	CONTRACTOR TO REMOVE EXISTING GLASS AND ITEMS IN DISPLAY CASE AND TURN OVER ITEMS TO OWNER'S REPRESENTATIVE. REMOVE EXISTING WOOD SILL FOR NEW SOLID SURFACE. PATCH, PAINT AND PRIME WALL TO MATCH ADJACENT SURFACES.

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

EXISTING PHOTOS

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND AS SUCH ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT FOR WHICH IT WAS PREPARED WITHOUT CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A503

GENERAL DOOR COMMENTS:

1. DOORS UNLISTED ON THE PLANS SHALL REMAIN AS IS.
2. CONTRACTOR SHALL COORDINATE THE INSTALLATION OF NEW DOORS, FRAMES AND HARDWARE w/ EXISTING CONDITIONS TO AVOID CONFLICTS AND CREATE THE REQUIRED ROUGH OPENING.
3. CONTRACTOR TO TURN OVER ALL EXISTING DOOR HARDWARE TO THE SERGEANT AT ARMS OR DISPOSE OF AS DIRECTED BY THE SERGEANT.
4. EXISTING DOORS THAT ARE NOTED TO BE DEMOLISHED MAY BE SALVAGED AND REUSED IF IN GOOD CONDITION.
5. ALL DOORS ON EGRESS PATH TO HAVE ADA COMPLIANT LEVER STYLE HANDLES.
6. FIELD VERIFY ALL OPENING SIZES PRIOR TO MANUFACTURING DOORS.
7. ALL NEW DOOR FINISH AND CONSTRUCTION SHALL MATCH EXISTING DOORS. CONTRACTOR TO PROVIDE SAMPLE TO MATCH EXISTING DOORS PRIOR TO MANUFACTURING DOORS.
8. PER NFPA 100, FINISHED FLOOR SURFACE ON BOTH SIDES OF ALL DOORS SHALL NOT VARY BY MORE THAN 1/2" FOR A DISTANCE NOT LESS THAN THE WIDEST DOOR LEAF.
9. ALL EXISTING AND NEW DOOR HARDWARE SHALL MATCH EXISTING. WHERE REPLACING EXISTING HARDWARE ON AN EXISTING DOOR TO REMAIN, PROVIDE A ONE-FOR-ONE REPLACEMENT. WHERE INSTALLING NEW HARDWARE ON NEW DOORS, PROVIDE HARDWARE TO MATCH SIMILAR FUNCTIONS.

DOOR SCHEDULED NOTES:

1. PROVIDE ADA COMPLIANT THRESHOLD AT DOOR.
2. INSTALL NEW POCKET DOOR AND HARDWARE IN 6" WALL CONSTRUCTION.
3. CASED OPENING, NO DOOR LEAF.
4. INSTALL NEW DOOR IN WALL CONSTRUCTION. VERIFY WALL THICKNESS. PROVIDE NEW HARDWARE TO MATCH NEW HARDWARE ON EXISTING DOORS.
5. REPLACE EXISTING DOOR HARDWARE ON DOOR. IN AREA OF WORK, A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, BUTTS & DOOR STOPS. CLEAN AND TOUCH-UP ALL STAINED DOORS. EXISTING DOOR FRAME SHALL REMAIN. EXISTING DOOR FRAME SHALL BE PAINTED TO MATCH NEW DOORS. EXISTING DOOR SHALL BE REMOVED, LABELED AND STORED FOR INSTALLATION AT LATER DATE.
6. CONTRACTOR TO REMOVE EXISTING DOOR AND PREP DOOR TO RECEIVE STAIN FINISH ON INTERIOR SIDE OF DOOR ONLY. STAIN FINISH SHALL MATCH DOOR FINISH IN MEETING RM 412.
7. CONTRACTOR TO REMOVE EXISTING DOOR AND PREP DOOR TO RECEIVE STAIN FINISH ON BOTH SIDES OF DOOR. STAIN FINISH SHALL MATCH DOOR FINISH IN MEETING RM 412.
8. REPLACE EXISTING DOOR HARDWARE ON DOOR. IN AREA OF WORK, A ONE-FOR-ONE REPLACEMENT TO INCLUDE LOCKSETS, EXIT DEVICES, CLOSERS, PUSH, PULLS, ADA PUSH BUTTONS, STRIKE PLATES, KICK PLATES, BUTTS & DOOR STOPS. EXISTING POWER OVER ETHERNET (POE) LOCK SHALL REMAIN. CLEAN AND TOUCH-UP ALL STAINED DOORS. EXISTING DOOR FRAME SHALL REMAIN. EXISTING DOOR FRAME SHALL BE PAINTED TO MATCH NEW DOORS. EXISTING DOOR SHALL BE REMOVED, LABELED AND STORED FOR INSTALLATION AT LATER DATE.
9. INSTALL NEW POWER OVER ETHERNET (POE) LOCK.



F1

SEE FRAME TYPES C1/A601 FOR INFORMATION OF FRAMES



HM2

C1 LEAF TYPES

SCALE: 1/4" = 1'-0"



B1 INTERIOR HM DOOR HEAD

SCALE: 3" = 1'-0"



A1 INTERIOR HM DOOR JAMB

SCALE: 3" = 1'-0"

C1 FRAME TYPES

SCALE: 1/4" = 1'-0"

ID	DOOR LEAF PROPERTIES					DOOR FRAME PROPERTIES			DETAILS		HW SET	NOTE
	TYPE	W x H	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB		
117A	ETR	6'-0"×6'-8"	1 3/4"	ETR	STAIN	ETR	ETR	ETR	ETR	ETR		1, 5, 6
117B	ETR	3'-0"×6'-8"	1 3/4"	ETR	STAIN	ETR	ETR	ETR	ETR	ETR		5, 6
118	ETR	3'-0"×6'-8"	1 3/4"	ETR	STAIN	ETR	ETR	ETR	ETR	ETR		5,7

F2 DOOR SCHEDULE - FIRST FLOOR

ID	DOOR LEAF PROPERTIES					DOOR FRAME PROPERTIES			DETAILS		HW SET	NOTE
	TYPE	W x H	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB		
215A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
215B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
215C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
215D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
215E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
215F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
215G	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT				4
215H	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	ETR	ETR		5
215I	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		3
215J	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4,9
225	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4, 9
225A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
225B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
225C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
225D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
225E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
227A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
227B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4

D2 DOOR SCHEDULE - SECOND FLOOR

ID	DOOR LEAF PROPERTIES					DOOR FRAME PROPERTIES			DETAIL		HW SET	NOTE
	TYPE	W x H	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB		
301	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
302	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
310A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
310B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
310C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
310D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
310E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
310F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
310G	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
312	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5, 9
314	ETR	6'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
315A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
315B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		10
315C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
315D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
315E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
315F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
320A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
320B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
320C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
320D	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
320E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
320F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
320G	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4, 9
325A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
325B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
325C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
325D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
325E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4, 9
325F	F1	2'-6"×6'-8"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		2
330A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4, 9
330B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
330C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
330D	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
330E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
335A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
335B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				8
335C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
337A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETRETR	ETR		8
337B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
339	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
343	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5

A2 DOOR SCHEDULE - THIRD FLOOR

DOOR ABBREVIATIONS:

ETR	= EXISTING TO REMAIN
F	= FLUSH
F.V.	= FIELD VERIFY
WD	= SOLID CORE WOOD

ID	DOOR LEAF PROPERTIES					DOOR FRAME PROPERTIES			DETAILS		HW SET	NOTE
	TYPE	W x H	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB		
401	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
402	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
410A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
410B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
410C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
410D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
410E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
410F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
414A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	ETR	ETR	ETR		5
414B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	ETR	ETR	ETR		5
415A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
415B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415G	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415H	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
415I	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
417	ETR	6'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
420A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
420B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
420C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
420D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
420E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
420F	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4, 9
420G	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
420H	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
426	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
430A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
430B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
430D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5

D5 DOOR SCHEDULE - FOURTH FLOOR

ID	DOOR LEAF PROPERTIES					DOOR FRAME PROPERTIES			DETAILS		HW SET	NOTE
	TYPE	W x H	THICKNESS	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB		
501	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
502	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		1, 5
510A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
510B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510G	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
510H	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
512	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
514	ETR	6'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
515A	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
515B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
515C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
515D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
515E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
515F	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
520A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
520B	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
520C	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
520D	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
520E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
520G	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4, 9
520H	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
525A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
525B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4, 9
525D	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
525E	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
525F	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5
525G	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
527	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
529	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
530A	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4, 9
530B	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		5
530C	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
530D	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
530E	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT	B1/A601	A1/A601		4
531	ETR	3'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		8
533	F1	3'-0"×7'-0"	1 3/4"	WD	STAIN	H2	HM	PAINT				4
537	ETR	6'-0"×7'-0"	1 3/4"	ETR	ETR	ETR	ETR	PAINT	ETR	ETR		5

A5 DOOR SCHEDULE - FIFTH FLOOR

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211

CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING
INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

DOOR SCHEDULES

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND IS FULLY PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE EXPRESS PURPOSE INTENDED WITHOUT THE CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2025 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A601

INTERIOR FINISHES

CARPET

	MANUFACTURER	COLLECTION	STYLE	COLOR	SIZE	ORIENTATION
C1	MANNINGTON	PALMA 2	PORTELA	SANTORINI	BROADLOOM	TBD, COORDINATE w/ ARCHITECT
C2	MATCH TO EXISTING CARPET					

LUXURY VINYL TILE

	MANUFACTURER	COLLECTION	STYLE	COLOR	SIZE & INSTALL PATTERN
LVT1	MANNINGTON	AMTICO SIGNATURE	WOOD	RECLAIMED OAK	MATCH EXISTING KITCHENS 312 & 512

NOTE: GLUE DOWN, AS SELECTED BY OWNER. TEST FLOOR SLAB FOR MOISTURE CONTENT PRIOR TO INSTALLING AND PREP FLOOR AS RECOMMENDED BY THE LVT MANUFACTURER.

FLOOR & BASE TILE

	MANUFACTURER	COLLECTION	COLOR NAME	COLOR NUMBER	SIZE	INSTALL PATTERN	GROUT COLOR
T1	DALTILE	VOLUME 1.0	AMPLIFY BLACK	VL70	12x12	GRID	G1

NOTE: INSTALL COORDINATING 6x12 BASE w/ FLOOR TILE. SEE INTERIOR ELEVATIONS.

NOTE: THROUGH-BODIED PORCELAIN TILE, SLIP-RESISTANT WHEN WET. THINSET. PROVIDE COORDINATING TILE BASE AROUND ROOM PERIMETER. SEE INTERIOR ELEVATIONS.

WALL TILE

	MANUFACTURER	COLLECTION	COLOR NAME	COLOR NUMBER	SIZE	INSTALL PATTERN	GROUT COLOR
T2	FLORIDA TILE	PRECIOUS	CALACATTA	FTI3500112X24	12x24	1/2 OFFSET - HORIZ.	G2

NOTE: INSTALL SCHLUTER TRIM, MATCH TO THE EXISTING BATHROOMS IN SENATE OFFICE BUILDING.

WOOD BASE

WD1 1x WOOD BASE, STAINED FINISH TO MATCH MEETING RM 412
WD2 1x WOOD BASE, STAINED FINISH TO MATCH EXISTING

CARPET WALL BASE

	MANUFACTURER	COLLECTION	STYLE	COLOR	LOCATION
CB1	MANNINGTON	PALMA 2	PORTELA	SANTORINI	@ ALL MAIN E & W HALLS

RUBBER WALL BASE

	MANUFACTURER	COLLECTION	STYLE	COLOR	LOCATION
R1	JOHNSONITE	MILLWORK	REVEAL 6"	63 BURNT UMBER	ALL OFFICE SUITES, WORK RM, & BREAK RM

GROUT

	MANUFACTURER	COLOR	LOCATION
G1	MAPEI	5047 CHARCOAL	w/ T1 TILE
G2	MAPEI	5103 COBBLESTONE	w/ T2 TILE

NOTE: TILE SPACING SHALL HAVE LESS THAN AN 1/8" GROUT JOINTS w/ 12"x24" AND 4"x12" TILES AND 3/32" GROUT JOINTS w/ SMALLER SIZED TILES

WINDOW SILLS

	MANUFACTURER	COLOR	LOCATION
CT1	CORIAN QUARTZ	WITCH HAZEL	LOCATED AT ALL WINDOW SILLS AS SHOWN ON THE FLOOR PLANS

COUNTERTOPS/ SOLID SURFACE

	MANUFACTURER	COLOR	LOCATION
CT1	CORIAN QUARTZ	WITCH HAZEL	TYPICAL COUNTERTOPS EXCEPT @ RESTROOMS
CT2	CAMBRIA	ROSE BAY	LOCATED IN RESTROOMS ONLY

LAMINATE

	MANUFACTURER	COLOR	FINISH	LOCATION
L1	WILSONART	4943 CLASSIC LINEN	38 FINE VELVET	ALL CABINETRY EXCEPT @ RESTROOMS
L2	TBD			BATHROOM VANITY PANEL & CABINETRY

PAINT COLOR

	MANUFACTURER	COLOR	FINISH	TYPICALLY USED ON
P1	SHERWIN WILLIAMS	EXTRA WHITE	FLAT	FLAT @ CEILINGS
P2	SHERWIN WILLIAMS	DOVER WHITE	EG-SHEL	TYPICAL WALL PAINT
P3	TBD			ACCENT PAINT @ WATER FOUNTAINS IN E & W HALLS
P4	MATCH EXISTING FRAME COLOR			TYPICAL DOOR FRAMES

TOILET PARTITION

MANUFACTURER	COLOR	TEXTURE
SCRANTON PRODUCTS	GREY	ORANGE PEEL

ACOUSTICAL CEILING TILE

	MANUFACTURER	COLLECTION	COLOR	LOCATION
ACT1	ARMSTRONG	ULTIMA, BEVELED TEGULAR	WHITE	TYPICAL UNLESS OTHERWISE NOTED

GENERAL FINISH COMMENTS:

1. EXTEND ALL WALLS TO THE STRUCTURAL DECK ABOVE AS NOTED IN THE FLOOR PLANS.
2. PREPARE ALL SUBSTRATES AS RECOMMENDED BY THE MANUFACTURER FOR THE FINAL FINISH PRODUCT.
3. PER FBC 1210.2.2, INSTALL MOISTURE RESISTANT GYPSUM BOARD AS NECESSARY. ALL WALL AND PARTITIONS WITHIN TWO (2) FEET OF ALL PLUMBING FIXTURES SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE, TO A HEIGHT OF NOT LESS THAN FOUR (4) FEET ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIALS USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE. ACCESSORIES SUCH AS GRAB BARS, TOWEL BARS, PAPER DISPENSERS, AND SOAP DISHES, PROVIDED ON OR WITHIN WALLS, SHALL BE INSTALLED AND SEALED TO PROTECT STRUCTURAL ELEMENTS FROM MOISTURE.
4. PER NFPA 100, FINISHED FLOOR SURFACE ON BOTH SIDES OF ALL DOORS SHALL NOT VARY BY MORE THAN 1/2" FOR A DISTANCE NOT LESS THAN THE WIDEST DOOR LEAF.
5. PROVIDE ADA COMPLIANT TRANSITION STRIP AT ALL CHANGES IN FLOOR FINISHES.
6. TERMINATE SCHEDULED FLOORING NEATLY AND FLUSH AT BUILT-IN CASEWORK, MILLWORK, OR FIXED FURNITURE BASES UNLESS OTHERWISE NOTED. PROVIDE CLEAN, STRAIGHT EDGE AT TERMINATIONS. FLOORING SHALL EXTEND BENEATH REMOVABLE FURNITURE AND EQUIPMENT.

FINISH SCHEDULE NOTES:

1. EXTEND GYPSUM BD. PARTITIONS TO THE STRUCTURAL DECK ABOVE AND INSULATE ENTIRE PARTITION AT WALLS NOTED ON THE FLOOR PLANS.
2. PROVIDE ADA COMPLIANT TRANSITION STRIPS AT ALL CHANGES IN FLOOR FINISHES. SET IN FULL BED OF SEALANT.
3. AT ENTRY TO MEN'S AND WOMENS' RESTROOMS INSTALL TILE FLOOR AND TILE BASE. WALLS IN THIS AREA SHALL BE PAINTED GYP. BD.
4. USE TILE BACKER BOARD BEHIND ALL WALL TILE.
5. ALL WALLS IN ALL RESTROOMS, UNLESS NOTED, TO BE TILED FLOOR-TO-CEILING. AT ALL EXPOSED TILE EDGES PROVIDE SCHLUTER TRIM.
6. CONTRACTOR TO PRIME AND PAINT ALL GYPSUM BOARD WALL SURFACES WITH TYPICAL PAINT COLOR.
7. EXISTING TILE FLOORS LOCATED AT WATER FOUNTAINS IN THE CORRIDOR SHALL REMAIN AS IS.

FINISH SCHEDULE ABBREVIATIONS:

ACT	= ACOUSTICAL CEILING TILE
ELEC	= ELECTRICAL ROOM
GYP	= GYPSUM BOARD
JC	= JANITOR'S CLOSET
LDRY	= LAUNDRY
LVT	= LUXURY VINYL TILE
MECH	= MECHANICAL ROOM
METAL	= METAL CEILING PANEL
RR	= RESTROOM
T&G	= TONGUE & GROOVE
VES.	= VESTIBULE

ROOM NO.	ROOM NAME	FLOOR		WALL		CEILING	NOTE
		FINISH	BASE	MATERIAL	FINISH		
117	COMMITTEE MEETING RM	C1	WD1	GYP	P2	ACT1; GYP	6
118	STOR.	C1	WD1	GYP	P2	ACT1	6

F3 FINISH SCHEDULE - FIRST FLOOR

ROOM NO.	ROOM NAME	FLOOR		WALL		CEILING	NOTE
		FINISH	BASE	MATERIAL	FINISH		
200A	E. HALL	C1	CB1	GYP	P2	ACT1	1, 6, 7
200B	ELEVATOR LOBBY	C1	CB1	GYP	P2	ACT1; GYP	6
200C	W. HALL	C1	CB1	GYP	P2	ACT1	6, 7
215A	HALL	C1	R1	GYP	P2	ACT1	6
215B	CONF.	C1	R1	GYP	P2	ACT1	1
215C	BREAK	LVT1	R1	GYP	P2	ACT1	2, 6
215D	OFFICE	C1	R1	GYP	P2	ACT1	6
215E	OFFICE	C1	R1	GYP	P2	ACT1	6
215F	OFFICE	C1	R1	GYP	P2	ACT1	6
215G	OFFICE	C1	R1	GYP	P2	ACT1	6
215H	HALL	C1	R1	GYP	P2	ACT1	6
225	RECEP.	C1	R1	GYP	P2	ACT1	1, 6
225A	OFFICE	C1	R1	GYP	P2	ACT1	6
225B	OFFICE	C1	R1	GYP	P2	ACT1	6
225C	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
225D	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
225E	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
227A	WORK RM	LVT1	R1	GYP	P2	GYP	2, 6
227B	BREAK	LVT1	R1	GYP	P2	GYP	2, 6

D3 FINISH SCHEDULE - SECOND FLOOR

ROOM NO.	ROOM NAME	FLOOR		WALL		CEILING	NOTE
		FINISH	BASE	MATERIAL	FINISH		
300A	E. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
300B	ELEVATOR LOBBY	C1	CB1	GYP	P2	ACT1; GYP	6
300C	W. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
300D	HALL	C1	CB1	GYP	P2	ACT1	6
301	WOMEN	T1	T1	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
302	MEN	T1	T1	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
310	HALL	C1	R1	GYP	P2	ACT1	6
310A	STOR	C1	R1	GYP	P2	ACT1	6
310B	RECEPTION	C1	R1	GYP	P2	ACT1	6
310C	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
310D	OFFICE	C1	R1	GYP	P2	ACT1	6
310E	OFFICE	C1	R1	GYP	P2	ACT1	6
310F	OFFICE	C1	R1	GYP	P2	ACT1	6
310G	STOR.	C1	R1	GYP	P2	ACT1	6
312	KITCHEN	ETR	ETR	ETR	ETR	ETR	
314	CONF.	C1	R1	GYP	P2	ACT1	1, 6
315	HALL	C1	R1	GYP	P2	ACT1	1, 6
315A	STOR	C1	R1	GYP	P2	ACT1	1, 6
315B	RECEPTION	C1	R1	GYP	P2	ACT1	6
315C	OFFICE	C1	R1	GYP	P2	ACT1	6
315D	OFFICE	C1	R1	GYP	P2	ACT1	6
315E	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
315F	STOR.	C1	R1	GYP	P2	GYP	6
320	HALL	C1	R1	GYP	P2	ACT1	6
320A	STOR.	C1	R1	GYP	P2	GYP	1, 6
320B	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
320C	OFFICE	C1	R1	GYP	P2	ACT1	6
320D	CONF.	C1	R1	GYP	P2	ACT1	6
320E	OFFICE	C1	R1	GYP	P2	ACT1	6
320F	OFFICE	C1	R1	GYP	P2	ACT1	6
320G	RECEP.	C1	R1	GYP	P2	ACT1	1, 6
325	HALL	C1	R1	GYP	P2	ACT1	6
325A	STOR.	C1	R1	GYP	P2	ACT1	6
325B	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
325C	OFFICE	C1	R1	GYP	P2	ACT1	6
325D	OFFICE	C1	R1	GYP	P2	ACT1	6
325E	RECEP.	C1	R1	GYP	P2	ACT1	6
325F	CONF.	C1	R1	GYP	P2	ACT1	1, 6
330A	RECEP.	C1	R1	GYP	P2	ACT1	1, 6
330B	OFFICE	C1	R1	GYP	P2	ACT1	6
330C	OFFICE	C1	R1	GYP	P2	ACT1	6
330D	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
330E	STOR.	C1	R1	GYP	P2	ACT1	1, 6
335A	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
335B	RECEP.	C1	R1	GYP	P2	ACT1	6
335C	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
337A	RECEP.	C1	R1	GYP	P2	ACT1	6
337B	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
339	OFFICE	C1	R1	GYP	P2	ACT1	6
343	WORK RM	LVT1	R1	GYP	P2	GYP	2, 6

A3 FINISH SCHEDULE - THIRD FLOOR

ROOM NO.	ROOM NAME	FLOOR		WALL		CEILING	NOTE
		FINISH	BASE	MATERIAL	FINISH		
400A	LOBBY	C1	WD2	GYP	P2	ACT1; GYP	6
400B	E. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
400C	ELEVATOR LOBBY	C1	CB1	GYP	P2	ACT1; GYP	1, 6
400D	W. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
401	WOMEN	T1	T1	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
402	MEN	T1	T1	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
410A	RECEPTION	C1	R1	GYP	P2	ACT1	6
410B	OFFICE	C1	R1	GYP	P2	ACT1	6
410C	OFFICE	C1	R1	GYP	P2	ACT1	6
410D	OFFICE	C1	R1	GYP	P2	ACT1	6
410E	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
410F	STOR.	C1	R1	GYP	P2	GYP	6
412C	MEETING ROOM	C2	WD1	GYP	P2	ETR	6
412D	MEETING ROOM	C2	WD1	GYP	P2	ETR	6
414	CONF.	C1	R1	GYP	P2	ACT1	1, 6
415A	RECEPTION	C1	R1	GYP	P2	ACT1	6
415B	OFFICE	C1	R1	GYP	P2	ACT1	6
415C	OFFICE	C1	R1	GYP	P2	ACT1	6
415D	OFFICE	C1	R1	GYP	P2	ACT1	6
415E	OFFICE	C1	R1	GYP	P2	ACT1	6
415F	OFFICE	C1	R1	GYP	P2	ACT1	6
415G	OFFICE	C1	R1	GYP	P2	ACT1	6
415H	OFFICE	C1	R1	GYP	P2	ACT1	6
415I	CONF.	C1	R1	GYP	P2	ACT1	6
417	WORK RM	LVT1	R1	GYP	P2	ACT1	2, 6
419A	GALLERY	C2	WD1	GYP	P2	ETR	6
419B	OFFICE 419	C2	WD1	GYP	P2	ETR	6
420A	OFFICE	C1	R1	GYP	P2	ACT1	6
420B	OFFICE	C1	R1	GYP	P2	ACT1	6
420C	CONF.	C1	R1	GYP	P2	ACT1	6
420D	OFFICE	C1	R1	GYP	P2	ACT1	6
420E	OFFICE	C1	R1	GYP	P2	ACT1	6
420F	RECEP.	C1	R1	GYP	P2	ACT1	1, 6
420G	OFFICE	C1	R1	GYP	P2	ACT1	6
420H	STOR.	C1	R1	GYP	P2	ACT1	6
426	CORRIDOR	C2	WD1	GYP	P2	ETR	2, 6
430A	RR	T1	T1	TILE	T2	ACT1	2, 4, 5
430B	RR	T1	T1	TILE	T2	ACT1	2, 4, 5
430D	BREAK ROOM	LVT1	R1	GYP	P2	ACT1	2, 6

D5 FINISH SCHEDULE - FOURTH FLOOR

ROOM NO.	ROOM NAME	FLOOR		WALL		CEILING	NOTE
		FINISH	BASE	MATERIAL	FINISH		
500A	E. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
500B	ELEVATOR LOBBY	C1	CB1	GYP	P2	GYP	6
500C	W. HALL	C1	CB1	GYP	P2	ACT1	2, 6, 7
501	WOMEN	T1	TILE	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
502	MEN	T1	TILE	GYP/TILE	T2; P2	ACT1	2, 3, 4, 5, 6
510A	RECEPTION	C1	R1	GYP	P2	ACT1	1, 6
510B	OFFICE	C1	R1	GYP	P2	ACT1	6
510C	OFFICE	C1	R1	GYP	P2	ACT1	6
510D	OFFICE	C1	R1	GYP	P2	ACT1	6
510E	OFFICE	C1	R1	GYP	P2	ACT1	6
510F	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
510G	STOR.	C1	R1	GYP	P2	GYP	6
512	KITCHEN	ETR	ETR	ETR	ETR	ETR	
514	CONF.	C1	R1	GYP	P2	ACT1	1, 6
515A	RECEPTION	C1	R1	GYP	P2	ACT1	1, 6
515B	OFFICE	C1	R1	GYP	P2	ACT1	6
515C	OFFICE	C1	R1	GYP	P2	ACT1	6
515D	OFFICE	C1	R1	GYP	P2	ACT1	6
515E	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
515F	STOR.	C1	R1	GYP	P2	ACT1	6
520A	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
520B	OFFICE	C1	R1	GYP	P2	ACT1	6
520C	OFFICE	C1	R1	GYP	P2	ACT1	6
520D	CONF.	C1	R1	GYP	P2	ACT1	6
520E	OFFICE	C1	R1	GYP	P2	ACT1	6
520F	HALL	C1	R1	GYP	P2	ACT1	6
520G	RECP.	C1	R1	GYP	P2	ACT1	1, 6
520H	STOR.	C1	R1	GYP	P2	ACT1	1, 6
525A	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
525B	RECEP.	C1	R1	GYP	P2	ACT1	6
525C	HALL	C1	R1	GYP	P2	ACT1	6
525D	OFFICE	C1	R1	GYP	P2	ACT1	6
525E	OFFICE	C1	R1	GYP	P2	ACT1	6
525F	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
525G	STOR.	C1	R1	GYP	P2	ACT1	6
527	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
529	OFFICE	C1	R1	GYP	P2	ACT1	1, 6
530A	RECEP.	C1	R1	GYP	P2	ACT1	1, 6
530B	OFFICE	C1	R1	GYP	P2	ACT1	6
530C	OFFICE	C1	R1	GYP	P2	ACT1	6
530D	OFFICE	C1	R1	GYP	P2	ACT1	6
530E	STOR.	C1	R1	GYP	P2	ACT1	1, 6
531	RECEPTION	C1	R1	GYP	P2	ACT1	6
533	OFFICE	C1	R1	GYP	P2	ACT1	6
537	WORK RM	LVT1	R1	GYP	P2	ACT1	2, 6

A5 FINISH SCHEDULE - FIFTH FLOOR

Dodstone Architects
3011-1 Powell Road
Tallahassee, FL 32308
850.656.7326
JOEL DODSON
AR0015211
CONSULTANT:

THE FLORIDA SENATE

KNOTT BUILDING INTERIOR RENOVATIONS

PROJECT NUMBER: 2025-0332

#	DATE	SUBMISSION TITLE
01	06/12/25	SCHEMATIC DESIGN
02	10/09/25	100% CONSTRUCTION DOCUMENTS
03	10/31/25	100% PERMIT DOCUMENTS

#	DATE	REVISION TITLE

FINISH SCHEDULES

AS INSTRUMENTS OF SERVICE, THESE DRAWINGS AND THE DESIGN ARE THE PROPERTY OF DODSTONE ARCHITECTS, INC. AND ARE PROTECTED BY STATE AND FEDERAL COPYRIGHT LAWS. REPRODUCTION OR USE OF THESE DRAWINGS OTHER THAN FOR THE PROJECT AT HAND WITHOUT THE EXPRESS CONSENT FROM DODSTONE ARCHITECTS, INC. IS PROHIBITED.
©2026 DODSTONE ARCHITECTS

REVIEWED BY: JD DRAWN BY: LS

A602